

AD-A045 320

DAVID W TAYLOR NAVAL SHIP RESEARCH AND DEVELOPMENT CE--ETC F/G 13/10  
TWIN CUSHION SURFACE EFFECT VEHICLE HEAD SEA REGULAR WAVE SEAKE--ETC(U)  
AUG 77 M J DAVIS, S H MCGUIGAN, D HUMINIK


UNCLASSIFIED

SPD-729-01

NL

1 OF 1  
AD  
A045320





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

SPD-729-01

**DAVID W. TAYLOR NAVAL SHIP  
RESEARCH AND DEVELOPMENT CENTER**

Bethesda, Md. 20084



AD A 045320

TWIN CUSHION SURFACE EFFECT VEHICLE HEAD  
SEA REGULAR WAVE SEAKEEPING EXPERIMENT


by

Michael J. Davis

Stephen H. McGuigan

Daniel Huminik

Jose A. Bonilla-Norat



APPROVED FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED

SHIP PERFORMANCE DEPARTMENT


TWIN CUSHION SURFACE EFFECT VEHICLE HEAD  
SEA REGULAR WAVE SEAKEEPING EXPERIMENT

AD No. \_\_\_\_\_  
DDC FILE COPY

August 1977

SPD-729-01

## MAJOR DTNSRDC ORGANIZATIONAL COMPONENTS



UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER SPD-729-01	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Twin Cushion Surface Effect Vehicle Head Sea Regular Wave Seakeeping Experiment.	5. TYPE OF REPORT & PERIOD COVERED Final Report	6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) Michael J. Davis, Stephen H. McGuigan, Daniel Humnik, Jose A. Bonilla-Norat	8. CONTRACT OR GRANT NUMBER(s)	
9. PERFORMING ORGANIZATION NAME AND ADDRESS David W. Taylor Naval Ship R&D Center Ship Performance Department Bethesda, Maryland 20084	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS Program Element 63564N Task Area S0407056 Task 20678 Work Unit 1102-003	
11. CONTROLLING OFFICE NAME AND ADDRESS Naval Sea Systems Command (0323) Washington, D. C.	12. REPORT DATE August 1977	13. NUMBER OF PAGES 86
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Systems Development Dept. Code 11 Advanced Naval Vehicle Concept Evaluation Program (ANVCE), David W. Taylor Naval Ship Research and Development Center, Bethesda, Maryland 20084	15. SECURITY CLASS. (of this report) Unclassified	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVED FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) S0407056		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Regular Waves; Seakeeping; Experimental Values		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Model experiments were performed to determine the head sea regular wave seakeeping characteristics of a Twin Cushion Surface Effect Vehicle. Experimental values of wave height, drag, cushion pressures and rigid body motions and accelerations are presented in graphical and tabular form.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE  
S/N 0102-010-6001

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

389694

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

1. TITLE	
2. AUTHOR	
3. PERIODICITY	
4. DATE	
5. SUBJECT	
6. ABSTRACT	
7. SUMMARY	
8. CONCLUSIONS	
9. REFERENCES	
10. DISTRIBUTION STATEMENT	
11. SECURITY CLASSIFICATION	
12. SECURITY CLASSIFICATION	
13. SECURITY CLASSIFICATION	
14. SECURITY CLASSIFICATION	
15. SECURITY CLASSIFICATION	
16. SECURITY CLASSIFICATION	
17. SECURITY CLASSIFICATION	
18. SECURITY CLASSIFICATION	
19. SECURITY CLASSIFICATION	
20. SECURITY CLASSIFICATION	
21. SECURITY CLASSIFICATION	
22. SECURITY CLASSIFICATION	
23. SECURITY CLASSIFICATION	
24. SECURITY CLASSIFICATION	
25. SECURITY CLASSIFICATION	
26. SECURITY CLASSIFICATION	
27. SECURITY CLASSIFICATION	
28. SECURITY CLASSIFICATION	
29. SECURITY CLASSIFICATION	
30. SECURITY CLASSIFICATION	
31. SECURITY CLASSIFICATION	
32. SECURITY CLASSIFICATION	
33. SECURITY CLASSIFICATION	
34. SECURITY CLASSIFICATION	
35. SECURITY CLASSIFICATION	
36. SECURITY CLASSIFICATION	
37. SECURITY CLASSIFICATION	
38. SECURITY CLASSIFICATION	
39. SECURITY CLASSIFICATION	
40. SECURITY CLASSIFICATION	
41. SECURITY CLASSIFICATION	
42. SECURITY CLASSIFICATION	
43. SECURITY CLASSIFICATION	
44. SECURITY CLASSIFICATION	
45. SECURITY CLASSIFICATION	
46. SECURITY CLASSIFICATION	
47. SECURITY CLASSIFICATION	
48. SECURITY CLASSIFICATION	
49. SECURITY CLASSIFICATION	
50. SECURITY CLASSIFICATION	
51. SECURITY CLASSIFICATION	
52. SECURITY CLASSIFICATION	
53. SECURITY CLASSIFICATION	
54. SECURITY CLASSIFICATION	
55. SECURITY CLASSIFICATION	
56. SECURITY CLASSIFICATION	
57. SECURITY CLASSIFICATION	
58. SECURITY CLASSIFICATION	
59. SECURITY CLASSIFICATION	
60. SECURITY CLASSIFICATION	
61. SECURITY CLASSIFICATION	
62. SECURITY CLASSIFICATION	
63. SECURITY CLASSIFICATION	
64. SECURITY CLASSIFICATION	
65. SECURITY CLASSIFICATION	
66. SECURITY CLASSIFICATION	
67. SECURITY CLASSIFICATION	
68. SECURITY CLASSIFICATION	
69. SECURITY CLASSIFICATION	
70. SECURITY CLASSIFICATION	
71. SECURITY CLASSIFICATION	
72. SECURITY CLASSIFICATION	
73. SECURITY CLASSIFICATION	
74. SECURITY CLASSIFICATION	
75. SECURITY CLASSIFICATION	
76. SECURITY CLASSIFICATION	
77. SECURITY CLASSIFICATION	
78. SECURITY CLASSIFICATION	
79. SECURITY CLASSIFICATION	
80. SECURITY CLASSIFICATION	
81. SECURITY CLASSIFICATION	
82. SECURITY CLASSIFICATION	
83. SECURITY CLASSIFICATION	
84. SECURITY CLASSIFICATION	
85. SECURITY CLASSIFICATION	
86. SECURITY CLASSIFICATION	
87. SECURITY CLASSIFICATION	
88. SECURITY CLASSIFICATION	
89. SECURITY CLASSIFICATION	
90. SECURITY CLASSIFICATION	
91. SECURITY CLASSIFICATION	
92. SECURITY CLASSIFICATION	
93. SECURITY CLASSIFICATION	
94. SECURITY CLASSIFICATION	
95. SECURITY CLASSIFICATION	
96. SECURITY CLASSIFICATION	
97. SECURITY CLASSIFICATION	
98. SECURITY CLASSIFICATION	
99. SECURITY CLASSIFICATION	
100. SECURITY CLASSIFICATION	

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

# TABLE OF CONTENTS

	Page
ABSTRACT	1
ADMINISTRATIVE INFORMATION	1
INTRODUCTION	2
DESCRIPTION OF MODEL AND TEST EQUIPMENT	2
MODEL	2
TEST EQUIPMENT	2
TEST PROGRAM AND PROCEDURE	5
DATA ANALYSIS	6
PRESENTATION AND DISCUSSION OF RESULTS	7
CONCLUSIONS	12
ACKNOWLEDGMENTS	13

ABSTRACT for	
NTM	White Section <input checked="" type="checkbox"/>
UNC	Off Section <input type="checkbox"/>
UNANNOUNCED	<input type="checkbox"/>
JUSTIFICATION	
BY	
DISTRIBUTION/AVAILABILITY CODES	
Dist.	AVAIL. and/or SPECIAL
A	

# LIST OF TABLES

	Page
Table 1 - Twin Cushion SEV Model Characteristics	14
Table 2 - Location of Transducers and Cushion Pressure Taps Twin Cushion SEV	15
Table 3a - 26 Kts Calm Water Minimum Analysis - Run 13 (Metric Units)	17
Table 3b - 26 Kts Calm Water Minimum Analysis - Run 13 (English Units)	18
Table 4a - 26 Kts Calm Water Minimum Analysis - Run 15 (Metric Units)	19
Table 4b - 26 Kts Calm Water Minimum Analysis - Run 15 (English Units)	20
Table 5 - 0 Kt Wave Amplitude (Metric Units)	21
Table 6 - 20 Kt Wave Amplitude (Metric Units)	22
Table 7 - 26 Kt Wave Amplitude (Metric Units)	23
Table 8 - 0 Kt Pitch (Metric Units)	24
Table 9 - 20 Kt Pitch (Metric Units)	25
Table 10 - 26 Kt Pitch (Metric Units)	26
Table 11 - 0 Kt Heave (Metric Units)	27
Table 12 - 20 Kt Heave (Metric Units)	28
Table 13 - 26 Kt Heave (Metric Units)	29
Table 14 - 0 Kt Bow Acceleration (Metric Units)	30
Table 15 - 20 Kt Bow Acceleration (Metric Units)	31
Table 16 - 26 Kt Bow Acceleration (Metric Units)	32
Table 17 - 0 Kt Relative Bow Motion (Metric Units)	33
Table 18 - 20 Kt Relative Bow Motion (Metric Units)	34
Table 19 - 26 Kt Relative Bow Motion (Metric Units)	35
Table 20 - 0 Kt Average Cushion Pressure (Metric Units)	36
Table 21 - 20 Kt Average Cushion Pressure (Metric Units)	37
Table 22 - 26 Kt Average Cushion Pressure (Metric Units)	38

# LIST OF TABLES (Cont'd)

	Page
Table 23 - 0 Kt Forward Cushion Pressure (Metric Units)	39
Table 24 - 20 Kt Forward Cushion Pressure (Metric Units)	40
Table 25 - 26 Kt Forward Cushion Pressure (Metric Units)	41
Table 26 - 0 Kt Aft Cushion Pressure (Metric Units)	42
Table 27 - 20 Kt Aft Cushion Pressure (Metric Units)	43
Table 28 - 26 Kt Aft Cushion Pressure (Metric Units)	44
Table 29 - 0 Kt Drag (Metric Units)	45
Table 30 - 20 Kt Drag (Metric Units)	46
Table 31 - 26 Kt Drag (Metric Units)	47
Table 32 - 0 Kt Wave Amplitude (English Units)	48
Table 33 - 20 Kt Wave Amplitude (English Units)	49
Table 34 - 26 Kt Wave Amplitude (English Units)	50
Table 35 - 0 Kt Heave (English Units)	51
Table 36 - 20 Kt Heave (English Units)	52
Table 37 - 26 Kt Heave (English Units)	53
Table 38 - 0 Kt Relative Bow Motion (English Units)	54
Table 39 - 20 Kt Relative Bow Motion (English Units)	55
Table 40 - 26 Kt Relative Bow Motion (English Units)	56
Table 41 - 0 Kt Average Cushion Pressure (English Units)	57
Table 42 - 20 Kt Average Cushion Pressure (English Units)	58
Table 43 - 26 Kt Average Cushion Pressure (English Units)	59
Table 44 - 0 Kt Forward Cushion Pressure (English Units)	60
Table 45 - 20 Kt Forward Cushion Pressure (English Units)	61
Table 46 - 26 Kt Forward Cushion Pressure (English Units)	62

# LIST OF TABLES (Cont'd)

	Page
Table 47 - 0 Kt Aft Cushion Pressure (English Units)	63
Table 48 - 20 Kt Aft Cushion Pressure (English Units)	64
Table 49 - 26 Kt Aft Cushion Pressure (English Units)	65
Table 50 - 0 Kt Drag (English Units)	66
Table 51 - 20 Kt Drag (English Units)	67
Table 52 - 26 Kt Drag (English Units)	68

## LIST OF FIGURES

	Page
Figure 1 - Twin Cushion SEV Model - Schematic of Transducer and Pressure Tap Locations	69
Figure 2 - Pitch Transfer Functions for 0, 20, 26 Knots	70
Figure 3 - Heave Transfer Functions for 0, 20, 26 Knots	71
Figure 4 - Bow Acceleration Transfer Functions for 0, 20, 26 Knots	72
Figure 5 - Relative Bow Motion Transfer Functions for 0, 20, 26 Knots	73
Figure 6 - Average Cushion Pressure Transfer Functions for 0, 20, 26 Knots	74
Figure 7 - Forward Cushion Pressure Transfer Functions for 0, 20, 26 Knots	75
Figure 8 - Aft Cushion Pressure Transfer Functions for 0, 20, 26 Knots	76
Figure 9 - Drag Transfer Functions for 0, 20, 26 Knots	77
Figure 10 - Mean Drag for 0, 20, 26 Knots	78
Figure 11 - Pitch Amplitude vs Wave Amplitude for 0, 20, 26 Knots	79
Figure 12 - Heave Amplitude vs Wave Amplitude for 0, 20, 26 Knots	80
Figure 13 - Bow Acceleration Amplitude vs Wave Amplitude for 0, 20, 26 Knots	81
Figure 14 - Relative Bow Motion Amplitude vs Wave Amplitude for 0, 20, 26 Knots	82
Figure 15 - Average Cushion Pressure Amplitude vs Wave Amplitude for 0, 20, 26 Knots	83
Figure 16 - Forward Cushion Pressure Amplitude vs Wave Amplitude for 0, 20, 26 Knots	85
Figure 17 - Aft Cushion Pressure Amplitude vs Wave Amplitude for 0, 20, 26 Knots	85
Figure 18 - Drag Amplitude vs Wave Amplitude for 0, 20, 26 Knots	86

### ABSTRACT

Model experiments were performed to determine the the sea-keeping characteristics of a Twin Cushion Surface Effect Vehicle in regular-wave head seas. Experimental values of wave height, drag, cushion pressures, and rigid body motions and accelerations are presented in graphical and tabular form.

### ADMINISTRATIVE INFORMATION

These experiments were performed in support of the Advanced Naval Vehicle Concept Evaluation (ANVCE) Program under Work Unit Number 1102-003. Funds were provided for this experiment by NAVSEA 0323, Task 20678, Task Area S0407056, Program Element 63564N.

## INTRODUCTION

The Ship Performance Department of the David W. Taylor Naval Ship Research and Development Center (DTNSRDC) performed head seas regular wave seakeeping experiments on a non-propelled dynamic model of a Twin Cushion Surface Effect Vehicle (SEV). These experiments were conducted at the DTNSRDC High Speed Basin in Langley, Virginia during June 1976. The purpose of these experiments was to determine the transfer functions and examine the linearity of the Twin Cushion SEV in head seas. This report presents a description of the model and equipment used; and the results obtained in a fairly limited number of experimental conditions. The results presented include mean, amplitude, phase and transfer function values in tabular form and nondimensionalized graphical plots of transfer functions.

## DESCRIPTION OF MODEL AND TEST EQUIPMENT

### Model

The Twin Cushion SEV model, as depicted in Figure 1, consists of two high length-to-beam ratio, deep-skirted hulls connected by a wing-form bridging structure. The bridging structure is constructed of reinforced styrofoam covered with fiberglass. The two hulls are hollow aluminum structures with fiberglass bow and stern section. The hulls house the fans and provide a plenum and supporting structure for the deep, slanted-pericell, nylon skirt system. The heave staff was attached through a pitch gimbal fixture to an aluminum channel located in the bridging structure of the model. This attachment was made at the nominal longitudinal and transverse center of gravity. This location and other model particulars are listed in Table 1.

### Test Equipment

The experiments were conducted at the DTNSRDC High Speed Basin in Langley, Virginia. This basin is 902 m (2960 ft) long and 7.3 m (24 ft) wide. When the wave maker is used the basin water level is lowered to 3 m (10 ft). The basin is filled with brackish water. The wave maker is a large vertical plate hinged at the basin bottom driven by a 10 speed truck transmission and reduction gear which is in turn powered by a DC motor. The speed of the DC motor is adjustable to provide a range of regular wave frequencies. Wave amplitude is determined by a combination of transmission gear setting and variation of the length of the stroke of the arm which connects the plate with the output crank of the reduction gear.

The towing carriage is powered by DC motors which drive the inflated rubber tires that support the carriage. The tires ride on rails formed by steel I-beams which extend the length of the basin. All personnel and equipment ride on the carriage.

The model was towed by the heave staff which was supported by bearings attached to a beam over the center bay of the carriage. Normally, the heave staff is allowed to surge, however, since this model was not propelled the heave staff was locked in surge.

Heave was measured using a linear string potentiometer. Pitch was measured using a high resolution film type potentiometer. Drag was measured by means of a "block gage", which is a cube shaped module containing flexures and a differential reluctance sensing element. The gage (rated at  $\pm 444.8$  N (100 lbf)) was installed in the heave staff directly above the pitch pivot. The relative locations of all transducers and pressure taps are shown in Figure 1 and listed in Table 2.

An ultrasonic transducer mounted on a fixture located on the bow of the port hull measured relative bow motion. An additional ultrasonic probe mounted on a staff, attached to the carriage forward of the model, measured wave height.

Force balance servo-accelerometers ( $\pm 5G$  range) were used to measure vertical accelerations at the bow and at the longitudinal center of gravity (LCG) of the port hull. The accelerometer at the LCG did not function properly; this was probably due to leakage of spray into its sealed connector.

Cushion pressures were measured using diaphragm-type pressure gages containing semi-conductor strain gages as the sensing element, and having a rated range of 4826 P (0.7 psi). The reference side of the pressure gages was connected to a constant (atmospheric) pressure chamber located on the carriage. Flexible tubing connected the active side of the gages to piezometer openings in the port hull. The forward and aft pressure gage piezometer openings were located directly within the bow and stern plenum areas of the port hull. The average pressure measurement was actually a combination of three piezometer openings located in cylindrical chambers which vented directly into the port hull plenum. These three piezometer openings were combined by flexible tubing to a manifold with a single output. The locations of these piezometer openings can be seen in Figure 1 and are listed in Table 2.

The transducer signals were amplified and all signals except the impact pressures were digitized using a system consisting of an Interdata Model 70 computer with 64 KB memory and selector channel, a nine-track Kennedy 3110 digital tape drive, an ASR 33 teletype, an Analogic 5800 analogue to digital (A to D) and digital to analogue (D to A) converter, a Versatec 1100A line printer, and a Tridata 1024 cartridge tape recorder.

A sample rate of 200 samples/channel/second was used and all channels into the digital system were filtered using 6-pole, Butterworth filters with a -3db point of 50 Hz. Wave amplitude, pitch, heave, drag, average (of three piezometers connected to a single gage) pressure, forward cushion pressure, relative bow motion, and mode channels were also recorded on Sanborn strip chart recorders to provide a continuous visual record of the signals. The mode channel is a step voltage provided by the computer to indicate the times during which a steady state condition existed and the computer was digitizing data. This period of time was manually controlled.

The two impact pressures, the two accelerations, mode, and waveheight were recorded on an oscillograph. The galvanometers used in the oscillograph have a natural frequency of 5 KHz and are flat out to 3 KHz. The signals into the oscillograph were unfiltered.

#### TEST PROGRAM AND PROCEDURE

The model was manually oscillated while on cushion at zero speed to determine its natural pitch and heave periods. The heave oscillation was accomplished by pushing down on the heave staff and then releasing the model and recording the motion on strip chart. Pitch oscillation was similarly accomplished by raising the stern of the model and then releasing it.

Prior to testing with the model, some runs (1-12) were made to sample the waves. These runs were analyzed and were compared with an informal calibration consisting of a limited frequency range of regular waves previously recorded for particular wavemaker settings. These wave runs and the comparisons were then used to predict appropriate wavemaker settings for the regular wave runs with the model.

The model experiments in regular waves were conducted only in head seas, because the towing carriage was not capable of accurately maintaining speed in the direction required for following seas. Model velocities of 0 knots, 20 kts, and 26 kts were used. The sequence in regular waves was to: position the carriage and model a few hundred feet down the basin, lower the model with fans on, collect a zero speed run, raise the model, back the carriage to the extreme starting point in the basin, lower the model, accelerate to 20 kts, collect data for a minimum of 10 cycles, accelerate to 26 kts, collect data until carriage operator signaled for deceleration to begin.

Ideally, a wavelength to wave height ratio of 100 should have been maintained for all regular wave experiments used to determine the transfer function. However, due to the relatively high velocities, and the consequent possibility of destruction of or damage to the model, wave-height was limited to approximately 0.1 m (4 in) for the range of wave frequencies used to determine the transfer functions. Larger waveheights were used later during the linearity check experiments in which wave height was varied while wave length was held as constant as wavemaker performance would allow. A few runs were made in calm water to characterize the calm water performance of the model.

#### Data Analysis

After each calm water run a minimum analysis consisting of mean ("d.c. level") standard deviation( $\sigma$ ), and root  $Q_0$  ( $\sqrt{2\sigma}$  i.e. the single amplitude if the wave form is sinusoidal) values in engineering units was performed for all channels input to the digital system. The root  $Q_0$  value in calm water was calculated to quantify the magnitude of any oscillation

about the mean value. After each pass in regular waves a minimum analysis and a harmonic analysis were performed for those portions of each run during which the strip charts indicated the waves to be regular (in some instances only a few cycles were found to be regular, probably due to basin interference with the waves). The harmonic analysis included determination of frequency of wave encounter, wave characteristics (period, frequency, length, etc.) and single amplitude and phase of model responses for the fundamental, second and third harmonics. The amplitudes were then used to calculate transfer functions values. These preliminary values were then plotted to begin definition of the transfer functions of the craft motions.

After completion of the experiment, further harmonic analyses were performed on each run, and wave lengths were calculated using finite depth formulas (as required by the combination of shallow depth and long waves). The portions of the run analyzed were further refined to allow analysis of as many cycles of data as wave regularity would allow. Transfer function values were again plotted and values which seemed contradictory or questionable were further verified by re-examination of the strip chart records and additional harmonic analysis if necessary.

The accelerations and impact pressures recorded on oscillograph were visually examined for the occurrence of impacting and extreme accelerations during those runs for which the wave steepness was most severe.

#### PRESENTATION AND DISCUSSION OF RESULTS

At zero speed, on-cushion with 20 fans operating the natural heave frequency of the model (as determined by manually oscillating the model) was approximately 1 Hz. The natural pitch frequency was approximately 1.2 Hz. These motions were heavily damped.

Tables 3 and 4 present minimum analyses for two calm water runs at 26 knots. Additional calm water runs were attempted at 32.6 knots, but this speed results in the model literally "flying" and the run was aborted to prevent model damage. The lift of the wing at this speed does not explain this behavior. This behavior may have been due to changes in air flow around the model caused by the close proximity of the carriage above the model.

Tables (5 - 7) present wave length to cushion length ratio, mean, root  $Q_0$ , amplitude (single), amplitude to root  $Q_0$  ratio, encounter period, wave period, and number of cycles for the wave amplitude channel for all the regular wave runs (dimensional quantities are in metric units). Tables 8 - 31 present these same values for pitch, heave, bow acceleration, relative bow motion, average cushion pressure, forward cushion pressure, aft cushion pressure and drag. In Tables 8 - 31 phase and transfer functions are also presented, while encounter period and wave period are omitted since these are constant for the particular run for all channels. Tables (5 - 31) present the values measured for the particular speed and measurement channel listed at the top of the page. For a particular channel the tables for the three speeds (0, 20, 26 knots) are presented consecutively, followed by those tables for the next measurement channel. Tables 32 - 52 repeat Tables 5 - 31 with dimensional quantities listed in English units when appropriate. Zero trim (mean pitch) represents the case with hull decks parallel to the water surface. Bow down motion is defined to be positive pitch. Zero sinkage (mean heave) and zero relative bow motion represent the model on cushion

in calm water with twenty fans operating. Heave is defined to be positive for model displacement down. Decreasing linear distance between bow and wave is defined as positive relative bow motion. Wave crests are taken to be positive.

The phases presented in Tables (5 - 52) are referenced to a zero phase which, by definition, exists when the maximum amplitude of a particular measurement occurs at the instant that the wave crest is at the model longitudinal center of gravity (LCG). A positive phase exists when the maximum amplitude of the particular measurement leads the maximum wave amplitude at the LCG.

The nondimensional transfer function values plotted in Figures 2 - 9 and listed in Tables 5 - 52 are defined in the following way:

- a. angular measurement:  $\text{angle}/\theta$
- b. displacement measurement:  $\text{displacement}/r$
- c. force measurement:  $\text{force} \times L_c/r\Delta$
- d. acceleration measurement:  $\text{acceleration} \times g/\omega_e^2 r$
- e. pressure measurement:  $\text{pressure} \times (L_c)^3/r\Delta$

where:

$\theta$  = maximum wave slope

$r$  = wave amplitude

$L_c$  = cushion length (2.17 m (7.12 ft) used)

$\Delta$  = model mass (65.8 kg (145 lbm) used)

$g$  = acceleration due to gravity ( $9.81 \text{ m/s}^2$  ( $32.2 \text{ ft/sec}^2$ ))

$\omega_e$  = measured frequency of wave encounter (rad/sec)

In some cases, comparison of the root  $Q_0$  and the amplitude obtained from the Fourier analysis or the ratio of the two for a particular run condition (see Tables 5 - 55) indicates large dis-

crepancies between these values. These two values would of course be expected to be approximately equal and their ratio close to one for a sinusoidal signal. Examination of the strip chart records indicates that the discrepancies between these two values are probably due to model or tow gear vibration or electrical interference. The strip chart records of bow acceleration show high frequency accelerations superimposed on the expected encounter frequency signal. These small amplitude accelerations are probably the result of fan induced and hull vibrations. It should be noted, however, that in some extreme wave amplitude conditions, short duration accelerations as high as twice the amplitude values listed in Tables 5 - 55 were noted. These accelerations were probably the result of the side hulls or cushion impacting the wave crest when the cushion nearly or completely collapsed. The drag measurement also contained high frequency oscillation which was caused by noticeable fore-aft vibration of the heave staff. During the earlier runs in the experiment, the relative bow motion measurement was contaminated by what was determined to be cable cross-talk from the fan power cable. All of these extraneous signals are, in effect, nearly entirely filtered by the Fourier analysis. The Fourier analysis was performed at what was determined to be the wave encounter frequency. Therefore, the amplitudes are in effect the amplitudes of wave induced phenomena at the encounter frequency.

The pitch oscillation during runs 319 and 331 was noted to have significant first and second harmonic content. During run 319 the first harmonic amplitude was approximately one-third of that of the fundamental amplitude and the second harmonic one-sixth. During run 331 both the first and second harmonic pitch amplitudes were approximately one-half of the fundamental

amplitude. This harmonic content in the pitch oscillation was also reflected in the relative bow motion for run 319, during which, the first harmonic amplitude was one-seventh of that of the fundamental and the second harmonic one-third of that of the fundamental. These were the only instances noted of appreciable first or second harmonic amplitude content during this experiment.

Figures 2 - 9 present plots of the transfer functions plotted versus the appropriate wave length to cushion length ratios (as listed in Tables 5 - 31). Figure 10 presents mean drag plotted versus wave length to cushion length (as listed in Tables 29 - 31 and 50 - 52). Figures 11 - 18 present plots of the measured signal amplitude versus wave amplitude for runs 320 - 322 and 353 - 367 during which wave length was held constant.

Some transfer function values can be seen (Figures 2 - 9) to vary significantly from the curves drawn. These variations appear to be due to nonlinearity of the craft motion for large wave amplitudes. The transfer function in many cases, particularly at zero speed, is multi peaked. The curves were drawn to adhere as closely as possible to those values for which the respective wave length to wave height ratio was close to 100. Lack of wave-maker calibration for the full range used made control of this ratio difficult. The variation in linearity is better illustrated in Figures 11 - 18 where nonlinearities can be seen at the higher wave amplitudes in pitch for the 20 kt speed (Figure 11). Variations in heave linearity at 0 knots and relative bow motion linearity at 20 knots can be seen in Figures 12 and 14. These variations are reflected in the bow acceleration linearity plots in Figure 13. However, the large variations seen in heave amplitude and relative bow motions (Figures 12 and 14) are not reflected in bow acceleration (Figure 13) due to the units and scale of the plot and the phase relationships between pitch and

heave. Combination of the measured pitch and heave, with particular regard to phase, results in values that correspond with the measured relative bow motion and bow acceleration. A large number of variations in the linearity study would be required to establish firm conclusions about the craft linearity.

Impacting of the bridging structure did not occur in the present tests. The ride-smoothing capability of the deep cushion appears responsible for this lack of impacting and the relatively low rigid body motions and accelerations measured in the severe (in respect to craft size and speed) conditions encountered by the craft in the linearity portions of this experiment.

As mentioned earlier, the majority of the tests to obtain the transfer functions were conducted in relatively mild waves of height about 1/100 of their length. During the linearity studies larger wave heights (up to about 12 inches) were examined in waves of length approximately 7 times the cushion length of the craft and waves of this height and length still produced no impacts. However, Figure 5 shows that the relative bow motion transfer function was approximately 3 at zero speed in  $\lambda/L_c = 2$  and at 20 kts in  $\lambda/L_c = 5$ . This indicates that a twelve inch wave height at these wave frequencies could have been critical since the height of the bridging structure above the bottom of the skirt was approximately 15 in (.038 m).

### CONCLUSIONS

This experiment was primarily concerned with defining the transfer functions and determining the linearity of the twin cushion SEV in head seas. To this end model experiments were performed in regular waves. The transfer functions are in many cases multi peaked. This is particularly noticeable at zero speed. Wide variations in linearity were recorded for some motions, such as heave. These variations did not drastically change the accelerations measured. This seems to be due to the phase relationship of the motions. The rigid body motions and accelerations measured appear low relative to the craft size, high speed, and large wave height conditions encountered during the experiment. This seems to be attributable to the ride smoothing capability of the deep cushion.

### ACKNOWLEDGMENTS

The authors wish to thank Mr. R. LeBeau of the Aviation and Surface Effect Department; and Messrs. S. Denny, R. Alder, J. Braxton, H. Holling, B. McCloud, G. Williford, Ms. R. Daube and other members of the staff at the DTNSRDC High Speed Basin, Langley, Virginia for their advice, cooperation, and participation in this experiment.

TABLE 1  
TWIN CUSHION SEV MODEL CHARACTERISTICS

	METRIC	ENGLISH
Length Overall	2.49 m	8.17 ft
Cushion Length	2.17 m	7.12 ft
Mass (Including heave staff)	5.9 kg (13 lbm)	68.5 kg 151 lbm
Cushion Fans		20
Fan Speed		365 rps
Longitudinal Center of Gravity (Aft of Leading Edge of Wing)	.405 m	1.33 ft
Transverse Center of Gravity		9

TABLE 2

LOCATION OF TRANSDUCERS AND CUSHION PRESSURE  
TAPS TWIN CUSHION SEV

1. C.G. Acceleration

- x 0.013 m (0.5 in) AFT of C.G.
- y 0.778 m (20.62 in) Port of C.G.
- z 0.019 m (0.75 in) Above Pontoon Deck

2. Forward Accelerometer

- x 1.311 m (51.62 in) Forward of C.G.
- y 0.638 m (24.12 in) Port of C.G.
- z 0.025 m (1.0 in) Above Port Hull Deck

3. Relative Bow Motion Sonic

- x 1.387 m (54.62 in) Forward of C.G.
- y 0.692 m (27.25 in) Port of C.G.
- z 0.146 m (5.75 in) Above Port Hull Deck

4. Forward Impact Gage

- x 0.127 m (5 in) Aft of Fwd Edge of Wing or 11 in (0.279 M)  
Fwd of C.G.
- y On Centerline
- z Lower side of Wing

5. C.G. (Mid) Impact Gage

- x 0.406 m (16 in) Aft of Fwd Edge of Wing (On C.G.)
- y On Centerline
- z Lower side of Wing

6. Forward Cushion Pressure

- x 0.864 m (34 in) Forward of C.G.
- y 0.533 m (21 in) Port of C.G.
- z On Plenum Diffuser

TABLE 2 (Cont'd)

LOCATION OF TRANSDUCERS AND CUSHION PRESSURE  
TAPS TWIN CUSHION SEV

7. Aft Cushion Pressure

- x 0.806 m (31.75 in) Aft of C.G.
- y 0.724 m (28.5 in) Port of C.G.
- z 0.019 m (0.75 in) Below Cushion Disperse (Wet Deck) or  
0.219 m (8.62 in) Below Pontoon Deck

8. Average Cushion Pressure

- x 0.800 m (31.5 in) Forward of C.G.
- y 0.927 m (36.5 in) Port of C.G.
- z Approximately .05 m (2 in) Below Pontoon Deck

9. Average Cushion Pressure

- x 0.165 m (6.5 in) Aft of C.G.
- y 0.959 m (37.75 in) Port of C.G.
- z Approximately .05 m (2 in) Below Pontoon Deck

10. Average Cushion Pressure

- x 0.698 m (27.5 in) Aft of C.G.
- y 0.927 m (36.5 in) Port of C.G.
- z Approximately .05 m (2 in) Below Pontoon Deck

11. Wave Amplitude Sonic

- x 4.95 m (16.25 ft) Forward of C.G.
- y 1.01 m (3.25 ft) Port of C.G.

Table 3a - 26 Kts Calm Water Minimum Analysis  
Run 13 (Metric Units)

Langley T1

19 June 1976

TWIN CUSHION SEV (ANVCE) REGULAR WAVE EXPERIMENT

MEAS SPEED = 26.25 KNOTS  
NOMN SPEED = 26.00 KNOTS

TIME: 0.000 - 23.360  
RECORDS: 1 - 146

RUN No 13

CHAN	KTS	CALIB	GAIN	MEAN	STDDEV	ROOTQO
1 CARR VEL	M	5.925E 00	1.000E 00	2.625E 01	8.404E-02	1.189E-01
2 WAVE AMP	DEG	2.540E-01	5.000E 00	-2.237E-03	1.513E-03	2.139E-03
3 PITCH	M	-2.000E 00	1.000E 00	3.897E-01	1.103E-01	1.560E-01
4 HEAVE	G	2.540E-01	5.000E 00	-2.901E-02	1.741E-03	2.463E-03
5 BOW ACC	G	4.000E 00	1.000E 01	5.281E-03	1.176E-01	1.664E-01
6 CG ACC	M	4.000E 00	1.000E 01	-1.708E-01	5.354E-02	7.572E-02
7 RBM	P	2.540E 01	5.000E 00	-5.174E-02	1.555E-03	2.199E-03
8 AVG PRES	P	4.826E 04	5.000E 01	3.035E 02	1.657E 01	2.344E 01
9 FWD PRES	P	4.826E 04	5.000E 01	2.896E 02	1.126E 01	1.593E 01
10 AFT PRES	P	4.826E 04	5.000E 01	2.679E 02	1.673E 01	2.367E 01
11 DRAG	N	-5.338E 01	2.000E 00	1.141E 02	6.766E 01	9.568E 01

Table 3b - 26 Kts Calm Water Minimum Analysis  
Run 13 (English Units)

18 JUNE 1976

TWIN CUSHION SEV (ANVCE) REGULAR WAVE EXPERIMENT

LANGLEY-T1

MEAS SPEED = 26.25 KNOTS  
NOMI SPEED = 26.00 KNOTS

RUN NO 13

TIME: 0.000 - 23.360  
RECORDS: 1 146

CHAR	CALIB	GAIN	MEAN	STDDEV	ROOT00
1 CARR VEL KTS	5.925E 00	1.000E 00	2.625E 01	8.404E-02	1.189E-01
2 WAVE AMP IN	1.000E 01	5.000E 00	-8.809E-02	5.956E-02	8.423E-02
3 PITCH DEG	-2.000E 00	1.000E 00	3.897E-01	1.103E-01	1.560E-01
4 HEAVE IN	1.000E 01	5.000E 00	-1.142E 00	6.855E-02	9.695E-02
5 BOW ACC G	4.000E 00	1.000E 01	5.281E-03	1.176E-01	1.664E-01
6 CG ACC G	4.000E 00	1.000E 01	-1.708E-01	5.354E-02	7.572E-02
7 RBH IN	1.000E 01	5.000E 00	-2.037E 00	6.123E-02	8.659E-02
8 AVG PRES PSI	7.000E 00	5.000E 01	4.402E-02	2.404E-03	3.399E-03
9 FWD PRES PSI	7.000E 00	5.000E 01	4.201E-02	1.633E-03	2.310E-03
10 AFT PRES PSI	7.000E 00	5.000E 01	3.885E-02	2.427E-03	3.433E-03
11 DRAG LBS	-1.200E 01	2.000E 00	2.566E 01	1.521E 01	2.151E 01

Table 4a - 26 Kts Calm Water Minimum Analysis  
Run 15 (Metric Units)

19 June 1976

Langley T1

Twin Cushion SEV (ANVCE) Regular Wave Experiments

MEAS SPEED = 26.28 KNOTS  
NOMN SPEED = 26.00 KNOTS

TIME: 0.000 - 23.520  
RECORDS: 1 - 147

RUN NO	15	CHAN	KTS	CALIB	GAIN	MEAN	STDDEV	ROOT00
1		CARR VEL	M	5.925E 00	1.000E 00	2.628E 01	8.376F-02	1.185E-01
2		WAVE AMP	DEG	2.540E 01	5.000E 00	-3.599E-03	1.944E-03	2.748E-03
3		PITCH	M	-2.000E 00	1.000E 00	9.740E-01	1.104E-01	1.561E-01
4		HEAVE	G	2.540E-01	5.000E 00	-5.771E-03	1.383E-03	1.956E-03
5		BOW ACC	G	4.000E 00	1.000E 01	3.709E-03	5.453E-02	7.711E-02
6		CG ACC	M	4.000E 00	1.000E 01	-6.043E-03	2.922E-02	4.13E-02
7		RBM	P	2.540E-01	5.000E 00	-2.082E-02	4.724E-03	6.683E-03
8		AVG PRES	P	4.826E 04	5.000E 01	2.840E 02	1.129E 01	1.596E 01
9		FWD PRES	P	4.826E 04	5.000E 01	3.055E 02	1.297E 01	1.835E 01
10		AFT PRES	P	4.826E 04	5.000E 01	2.834E 02	1.126E 01	1.593E 01
11		DRAG	N	-5.338E 01	2.000E 00	1.229E 02	5.907E 01	8.354E 01

Table 4b - 26 Kts Calm Water Minimum Analysis  
Run 15 (English Units)

LANGLEY T1		TWIN CUSHION SEV (ANVCE) REGULAR WAVE EXPERIMENT		19 JUNE 1976	
RUN NO 15		MEAS SPEED - 26.28 KNOTS NOVA SPEED - 26.00 KNOTS		TIME: 0.000 - 23.520 RECORDS: 1 - 147	
CHAN		CALIB	GAIN	MEAN	STDDEV
1	CARR VEL	5.925E 00	1.000E 00	2.628E 01	0.370E-02
2	WAVE AMP	1.000E 01	5.000E 00	-1.401E-01	7.650E-02
3	PITCH	-2.000E 00	1.000E 00	9.740E-01	1.104E-01
4	HEAVE	1.000E 01	5.000E 00	-2.272E-01	5.446E-02
5	BOU ACC	4.000E 00	1.000E 01	3.709E-03	5.453E-02
6	CG ACC	4.000E 00	1.000E 01	-6.043E-03	2.922E-02
7	RBH	1.000E 01	5.000E 00	-8.197E-01	1.860E-01
8	AVG PRES	7.000E 00	5.000E 01	4.119E-02	1.637E-03
9	FUD PRES	7.000E 00	5.000E 01	4.431E-02	1.801E-03
10	AFT PRES	7.000E 00	5.000E 01	4.110E-02	1.633E-03
11	DRAG	-1.200E 01	2.000E 00	2.764E 01	1.320E 01
					ROOT00
					1.185E-01
					1.802E-01
					1.561E-01
					7.702E-02
					7.711E-02
					4.132E-02
					2.631E-01
					2.315E-03
					2.661E-03
					2.310E-03
					1.878E 01

Table 5 - 0 Kt Wave Amplitude (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

WAVE AMPLITUDE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (METERS)	ROOTQ0 (METERS)	AMPLITUDE (METERS)	AMPLITUDE /ROOTQ0	ENCOUNTER PERIOD	WAVE PERIOD	NUMBER CYCLES
300	1.491	2.753E-03	2.044E-02	2.000E-02	9.78E-01	1.455	1.455	11.
344	1.499	-3.724E-03	2.177E-02	2.146E-02	9.86E-01	1.444	1.444	4.
347	1.750	-3.874E-03	1.862E-02	1.820E-02	9.77E-01	1.560	1.560	2.
302	2.290	-8.174E-04	3.774E-02	3.749E-02	9.93E-01	1.784	1.784	5.
350	2.360	-2.121E-03	2.891E-02	2.791E-02	9.65E-01	1.812	1.812	5.
305	2.969	-4.176E-03	3.724E-02	3.691E-02	9.91E-01	2.037	2.037	6.
308	3.933	-1.332E-03	5.014E-02	4.976E-02	9.92E-01	2.365	2.365	6.
311	4.564	-2.809E-03	5.438E-02	5.403E-02	9.94E-01	2.571	2.571	5.
314	5.332	-2.657E-03	4.529E-02	4.460E-02	9.85E-01	2.826	2.826	4.
317	6.488	-2.990E-03	5.832E-02	5.779E-02	9.91E-01	3.203	3.203	6.
320	7.206	-3.465E-03	7.198E-02	7.092E-02	9.85E-01	3.458	3.458	4.
356	7.248	-2.355E-03	5.075E-02	5.032E-02	9.80E-01	3.473	3.473	5.
359	7.272	-3.218E-03	6.810E-02	6.594E-02	9.68E-01	3.481	3.481	5.
362	7.291	-6.482E-03	9.268E-02	9.020E-02	9.73E-01	3.488	3.488	5.
353	7.333	-9.817E-04	2.550E-02	2.473E-02	9.70E-01	3.492	3.492	5.
365	7.433	-9.672E-03	1.316E-01	1.266E-01	9.62E-01	3.525	3.525	5.
326	8.057	-1.833E-03	7.348E-02	7.211E-02	9.81E-01	3.750	3.750	1.
368	8.078	2.758E-03	6.261E-02	6.132E-02	9.79E-01	3.758	3.758	5.
329	8.253	-2.277E-03	5.857E-02	5.718E-02	9.76E-01	3.820	3.820	3.
335	8.336	-1.470E-03	4.854E-02	4.569E-02	9.42E-01	3.850	3.850	4.
332	8.553	-2.123E-03	6.322E-02	6.142E-02	9.72E-01	3.929	3.929	2.
338	8.881	-3.391E-03	4.397E-02	4.298E-02	9.77E-01	4.026	4.026	1.

Table 6 - 20 Kt Wave Amplitude (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

WAVE AMPLITUDE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (METERS)	ROOTQ0 (METERS)	AMPLITUDE (METERS)	AMPLITUDE /ROOTQ0	ENCOUNTER PERIOD	WAVE PERIOD	NUMBER CYCLES
345	1.489	-5.255E-03	2.149E-02	2.079E-02	9.68E-01	.256	1.439	13.
301	1.506	-3.033E-03	1.983E-02	1.972E-02	9.94E-01	.259	1.447	15.
342	1.530	1.243E-04	4.732E-03	3.846E-03	8.13E-01	.262	1.458	11.
348	1.757	-4.940E-03	2.438E-02	2.302E-02	9.44E-01	.298	1.563	10.
351	2.243	-3.338E-03	3.239E-02	3.030E-02	9.35E-01	.370	1.766	8.
303	2.273	-1.494E-03	3.058E-02	2.863E-02	9.36E-01	.375	1.778	18.
306	2.938	-4.498E-03	3.802E-02	3.655E-02	9.61E-01	.474	2.026	12.
309	3.790	-3.409E-03	5.110E-02	5.029E-02	9.84E-01	.599	2.317	4.
312	4.360	-3.317E-03	4.981E-02	4.928E-02	9.89E-01	.686	2.506	12.
315	5.073	-4.732E-03	4.630E-02	4.440E-02	9.59E-01	.800	2.740	5.
318	5.790	-3.048E-03	5.022E-02	4.884E-02	9.73E-01	.921	2.976	12.
354	6.233	-4.727E-03	2.293E-02	2.149E-02	9.37E-01	.997	3.120	4.
366	6.260	-1.007E-02	1.575E-01	1.510E-01	9.59E-01	1.001	3.128	3.
360	6.290	-6.647E-03	7.640E-02	7.366E-02	9.64E-01	1.007	3.138	3.
357	6.361	-5.319E-03	4.255E-02	4.158E-02	9.77E-01	1.019	3.162	5.
363	6.372	-7.823E-03	1.271E-01	1.236E-01	9.72E-01	1.022	3.165	3.
321	6.397	-4.610E-03	6.266E-02	6.048E-02	9.65E-01	1.026	3.730	8.
327	6.786	1.031E-03	6.726E-02	6.513E-02	9.68E-01	1.100	3.312	4.
370	6.899	-8.392E-03	6.546E-02	6.441E-02	9.84E-01	1.122	3.351	8.
330	6.922	-3.856E-03	6.985E-02	6.802E-02	9.74E-01	1.127	3.359	4.
333	7.242	-3.020E-03	6.607E-02	6.330E-02	9.58E-01	1.190	3.471	3.
336	7.393	-2.972E-03	6.238E-02	5.992E-02	9.60E-01	1.213	3.512	7.
339	7.468	-3.236E-03	6.474E-02	6.200E-02	9.58E-01	1.228	3.537	7.

Table 7 - 26 Kt Wave Amplitude (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

WAVE AMPLITUDE

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (METERS)	ROOTQ0 (METERS)	AMPLITUDE (METERS)	AMPLITUDE /ROOTQ0	ENCOUNTER PERIOD	WAVE PERIOD	NUMBER CYCLES
343	1.213	-5.748E-03	2.266E-02	2.237E-02	9.87E-01	.170	1.299	2.
346	1.495	-2.291E-03	2.191E-02	2.150E-02	9.81E-01	.206	1.442	9.
349	1.741	-1.273E-03	2.358E-02	2.318E-02	9.83E-01	.237	1.556	8.
304	2.222	-9.055E-04	3.030E-02	2.982E-02	9.84E-01	.297	1.758	16.
352	2.263	-1.453E-03	3.251E-02	3.000E-02	9.23E-01	.302	1.771	26.
307	2.930	-3.863E-03	3.673E-02	3.586E-02	9.77E-01	.384	2.023	10.
310	3.813	-1.654E-03	5.121E-02	5.100E-02	9.96E-01	.493	2.325	10.
313	4.341	-4.013E-03	5.255E-02	5.088E-02	9.83E-01	.560	2.498	12.
316	5.001	-5.471E-03	4.879E-02	4.658E-02	9.55E-01	.647	2.711	10.
319	5.930	-6.248E-03	5.027E-02	4.628E-02	9.21E-01	.782	3.020	7.
355	6.272	-1.453E-03	2.733E-02	2.624E-02	9.60E-01	.832	3.132	3.
358	6.326	-5.712E-03	4.407E-02	4.293E-02	9.74E-01	.841	3.150	9.
361	6.387	-6.109E-03	8.250E-02	8.095E-02	9.81E-01	.850	3.170	5.
322	6.393	-5.298E-03	6.599E-02	5.756E-02	8.72E-01	.860	3.190	9.
364	6.433	-3.007E-03	1.277E-01	1.241E-01	9.72E-01	.857	3.185	8.
328	6.757	-8.979E-05	7.054E-02	6.952E-02	9.86E-01	.912	3.302	17.
331	6.905	-2.462E-03	7.231E-02	7.059E-02	9.76E-01	.936	3.353	5.
334	7.175	-1.870E-03	6.830E-02	6.576E-02	9.63E-01	.982	3.447	5.
337	7.242	-1.645E-03	6.761E-02	6.612E-02	9.78E-01	.994	3.471	5.
340	7.451	-2.708E-03	6.406E-02	6.172E-02	9.64E-01	1.024	3.532	10.

Table 8 - 0 Kt Pitch (Metric Units)

TWIN CUSHION SEV  
REGULAR WAVE DATA

JUNE 1976

PITCH  
NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (DEG)	ROOTQ0 (DEG)	AMPLITUDE (DEG)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	-7.252E-01	1.153E+00	1.141E+00	80.1	5.23E-01	9.89E-01	11.
344	1.499	-1.510E-01	1.284E+00	1.262E+00	70.8	5.32E-01	9.83E-01	4.
347	1.750	-3.150E-01	1.600E+00	1.596E+00	73.3	9.25E-01	9.97E-01	2.
302	2.290	-4.471E-01	1.141E+00	1.137E+00	85.5	4.18E-01	9.96E-01	5.
350	2.360	-2.933E-01	1.805E+00	1.735E+00	59.6	8.85E-01	9.61E-01	5.
305	2.969	-1.505E+00	1.858E+00	1.854E+00	72.4	8.98E-01	9.98E-01	6.
308	3.933	-1.032E-01	1.758E+00	1.752E+00	82.9	8.35E-01	9.96E-01	6.
311	4.564	-1.246E+00	1.521E+00	1.507E+00	76.6	7.67E-01	9.91E-01	5.
314	5.332	-1.405E+00	1.373E+00	1.344E+00	50.3	9.69E-01	9.79E-01	4.
317	6.488	-1.287E+00	1.216E+00	1.177E+00	79.8	7.97E-01	9.68E-01	6.
320	7.206	-1.592E+00	1.687E+00	1.665E+00	86.2	1.02E+00	9.87E-01	4.
356	7.248	-5.229E-01	1.062E+00	1.049E+00	85.7	9.11E-01	9.88E-01	5.
359	7.272	-5.828E-01	1.537E+00	1.486E+00	62.8	9.88E-01	9.67E-01	5.
362	7.291	-6.008E-01	2.820E+00	2.700E+00	67.9	1.31E+00	9.57E-01	5.
353	7.333	-7.745E-01	6.912E-01	6.583E-01	84.3	1.17E+00	9.52E-01	5.
365	7.433	9.760E-02	3.218E+00	3.091E+00	66.1	1.09E+00	9.61E-01	5.
326	8.057	-2.511E-01	1.629E+00	1.585E+00	80.1	1.06E+00	9.73E-01	1.
368	8.078	-9.364E-01	1.264E+00	1.181E+00	73.3	9.37E-01	9.35E-01	5.
329	8.253	-1.978E-01	1.392E+00	1.339E+00	69.2	1.17E+00	9.62E-01	3.
335	8.336	-1.998E-01	1.048E+00	9.770E-01	75.5	1.07E+00	9.33E-01	4.
332	8.553	7.240E-02	1.544E+00	1.475E+00	77.3	1.24E+00	9.55E-01	2.
338	8.881	-1.777E-01	8.274E-01	8.061E-01	70.9	1.00E+00	9.74E-01	1.

Table 9 - 20 Kt Pitch (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

PITCH

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (DEG)	ROOTQ0 (DEG)	AMPLITUDE (DEG)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	6.693E-01	4.179E-01	1.861E-01	344.5	8.03E-02	4.45E-01	13.
301	1.506	1.159E-01	3.881E-01	1.637E-01	330.2	7.53E-02	4.22E-01	15.
342	1.530	7.786E-01	3.420E-01	1.173E-01	198.2	2.81E-01	3.43E-01	11.
348	1.757	1.249E-01	9.711E-01	8.977E-01	290.4	4.13E-01	9.24E-01	10.
351	2.243	2.991E-02	1.120E+00	1.002E+00	33.0	4.47E-01	8.95E-01	8.
303	2.273	3.797E-01	7.919E-01	6.199E-01	19.7	2.97E-01	7.83E-01	18.
306	2.938	-7.909E-01	9.224E-01	8.167E-01	24.7	3.96E-01	8.85E-01	12.
309	3.790	-1.547E-01	1.124E+00	9.079E-01	32.2	4.12E-01	8.08E-01	4.
312	4.360	-4.867E-01	1.137E+00	1.048E+00	24.9	5.59E-01	9.22E-01	12.
315	5.073	-3.417E-01	1.213E+00	1.125E+00	32.1	7.75E-01	9.27E-01	5.
318	5.790	-2.665E-03	1.254E+00	1.169E+00	49.7	8.36E-01	9.33E-01	12.
354	6.233	2.600E-01	7.798E-01	6.649E-01	66.3	1.16E+00	8.53E-01	4.
366	6.260	6.975E-01	1.965E+00	1.077E+00	65.4	2.69E-01	5.48E-01	3.
360	6.290	2.273E-01	1.839E+00	1.692E+00	69.4	8.71E-01	9.20E-01	3.
357	6.361	3.267E-01	1.208E+00	1.125E+00	63.9	1.03E+00	9.32E-01	5.
363	6.372	2.278E-01	2.086E+00	1.638E+00	51.2	5.09E-01	7.85E-01	3.
321	6.397	-1.719E-01	1.568E+00	1.475E+00	60.2	9.41E-01	9.41E-01	8.
327	6.786	9.253E-01	1.460E+00	1.420E+00	70.9	8.92E-01	9.72E-01	4.
370	6.899	-2.033E+00	1.712E+00	1.603E+00	90.1	1.04E+00	9.37E-01	8.
330	6.922	1.033E+00	1.565E+00	1.500E+00	74.5	9.20E-01	9.59E-01	4.
333	7.242	8.503E-01	1.607E+00	1.492E+00	76.8	1.03E+00	9.28E-01	3.
336	7.393	1.095E+00	1.514E+00	1.416E+00	79.3	1.05E+00	9.35E-01	7.
339	7.468	1.067E+00	1.523E+00	1.424E+00	84.1	1.03E+00	9.35E-01	7.

Table 10 - 26 Kt Pitch (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

PITCH

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (DEG)	ROOTQ0 (DEG)	AMPLITUDE (DEG)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	-1.814E-01	2.165E-01	4.631E-02	326.1	1.51E-02	2.14E-01	2.
346	1.495	1.062E-01	1.928E-01	1.025E-01	313.5	4.30E-02	5.32E-01	9.
349	1.741	-1.535E+00	3.124E-01	2.379E-01	303.4	1.08E-01	7.61E-01	8.
304	2.222	-1.518E+00	2.280E+00	2.229E+00	328.3	1.00E+00	9.78E-01	16.
352	2.263	-1.310E+00	2.880E+00	2.668E+00	346.7	1.21E+00	9.26E-01	26.
307	2.930	-2.161E+00	1.199E+00	1.162E+00	40.7	5.72E-01	9.70E-01	10.
310	3.813	-1.935E+00	1.174E+00	1.054E+00	69.1	4.75E-01	8.97E-01	10.
313	4.341	-1.652E+00	1.006E+00	7.659E-01	87.9	3.88E-01	7.61E-01	12.
316	5.001	-8.678E-01	5.899E-01	3.478E-01	81.8	2.25E-01	5.90E-01	10.
319	5.930	-6.554E-01	5.513E+01	2.593E-01	65.9	2.00E-01	4.70E-01	7.
355	6.272	-4.817E-01	2.765E-01	1.864E-01	81.4	2.69E-01	6.74E-01	3.
358	6.326	-3.724E-01	5.243E-01	3.222E-01	77.7	2.86E-01	6.15E-01	9.
361	6.387	-8.962E-01	9.083E-01	7.756E-01	94.9	3.69E-01	8.54E-01	5.
322	6.393	-1.151E+00	6.514E-01	4.813E-01	81.9	3.22E-01	7.39E-01	9.
364	6.433	-1.426E+00	1.486E+00	1.222E+00	109.4	3.82E-01	8.22E-01	8.
328	6.757	3.694E-01	5.804E-01	4.463E-01	65.0	2.62E-01	7.69E-01	17.
331	6.905	3.610E-01	6.729E-01	3.088E-01	43.6	1.82E-01	4.59E-01	5.
334	7.175	4.504E-01	7.210E-01	5.965E-01	68.5	3.92E-01	8.27E-01	5.
337	7.242	7.181E-01	7.325E-01	6.050E-01	51.7	3.99E-01	8.26E-01	5.
340	7.451	4.778E-01	7.648E-01	6.179E-01	65.9	4.50E-01	8.08E-01	10.

Table 11 - 0 Kt Heave (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

HEAVE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (METERS)	ROOTQ0 (METERS)	AMPLITUDE (METERS)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	8.570E-03	8.936E-03	8.435E-03	181.2	4.22E-01	9.44E-01	11.
344	1.499	1.827E-02	1.042E-02	1.021E-02	181.2	4.76E-01	9.80E-01	4.
347	1.750	2.764E-02	1.747E-02	1.743E-02	187.9	9.58E-01	9.98E-01	2.
302	2.291	1.154E-02	2.153E-02	2.124E-02	175.1	5.66E-01	9.87E-01	5.
350	2.360	6.426E-02	2.196E-02	2.108E-02	169.4	7.55E-01	9.60E-01	5.
305	2.969	5.438E-03	2.786E-02	2.771E-02	176.4	7.51E-01	9.94E-01	6.
308	3.933	1.599E-02	4.694E-02	4.681E-02	181.8	9.41E-01	9.97E-01	6.
311	4.564	1.208E-02	4.958E-02	4.933E-02	175.0	9.13E-01	9.95E-01	5.
314	5.332	2.215E-02	4.752E-02	4.704E-02	168.7	1.05E+00	9.90E-01	4.
317	6.488	2.888E-02	5.034E-02	4.996E-02	157.8	8.65E-01	9.93E-01	6.
320	7.206	2.277E-02	5.197E-02	5.126E-02	164.8	7.23E-01	9.87E-01	4.
356	7.248	1.627E-02	3.734E-02	3.698E-02	159.8	7.35E-01	9.90E-01	5.
359	7.272	1.123E-02	8.730E-02	8.484E-02	165.9	1.29E+00	9.72E-01	5.
362	7.291	9.068E-03	1.219E-01	1.189E-01	-175.4	1.32E+00	9.75E-01	5.
353	7.333	1.563E-02	1.688E-02	1.662E-02	189.3	6.72E-01	9.85E-01	5.
365	7.433	1.849E-02	1.677E-01	1.633E-01	172.2	1.29E+00	9.73E-01	5.
326	8.057	1.127E-02	6.106E-02	5.992E-02	163.2	8.31E-01	9.81E-01	1.
368	8.078	1.420E-02	6.906E-02	6.792E-02	160.0	1.11E+00	9.83E-01	5.
329	8.253	8.517E-03	7.684E-02	7.526E-02	-178.1	1.32E+00	9.79E-01	3.
335	8.336	1.189E-02	7.295E-02	6.866E-02	189.9	1.50E+00	9.41E-01	4.
332	8.553	1.338E-02	5.753E-02	5.603E-02	198.7	9.13E-01	9.74E-01	2.
338	8.881	1.584E-02	7.534E-02	7.485E-02	179.8	1.74E+00	9.94E-01	1.

Table 12 - 20 Kt Heave (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

HEAVE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (METERS)	ROOTQ0 (METERS)	AMPLITUDE (METERS)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	8.369E-03	5.044E-03	3.513E-03	62.5	1.69E-01	6.96E-01	13.
301	1.506	2.026E-02	3.914E-03	3.348E-03	47.6	1.70E-01	8.55E-01	15.
342	1.530	2.483E-04	1.855E-03	5.519E-04	65.5	1.44E-01	2.97E-01	11.
348	1.757	1.289E-02	9.428E-03	7.442E-03	79.8	3.23E-01	7.90E-01	10.
351	2.243	1.453E-02	2.082E-02	1.702E-02	93.8	5.62E-01	8.17E-01	8.
303	2.273	1.227E-02	2.264E-02	1.738E-02	89.2	6.07E-01	7.68E-01	18.
306	2.938	1.626E-02	3.820E-02	3.556E-02	112.1	9.73E-01	9.31E-01	12.
309	3.790	1.371E-02	6.190E-02	6.121E-02	137.2	1.22E+00	9.89E-01	4.
312	4.360	1.383E-02	6.693E-02	6.632E-02	146.4	1.35E+00	9.91E-01	12.
315	5.073	1.651E-02	6.261E-02	6.035E-02	156.7	1.36E+00	9.64E-01	5.
318	5.790	9.865E-03	6.322E-02	6.210E-02	174.8	1.27E+00	9.82E-01	12.
354	6.233	9.924E-03	2.878E-02	2.751E-02	180.4	1.28E+00	9.56E-01	4.
366	6.260	8.319E-03	2.088E-01	2.040E-01	176.7	1.35E+00	9.77E-01	3.
360	6.290	1.178E-02	9.487E-02	9.205E-02	187.6	1.25E+00	9.70E-01	3.
357	6.361	6.345E-03	5.441E-02	5.331E-02	182.0	1.28E+00	9.80E-01	5.
363	6.372	7.790E-03	1.451E-01	1.419E-01	174.4	1.15E+00	9.78E-01	3.
321	6.397	1.245E-02	7.752E-02	7.546E-02	179.2	1.25E+00	9.74E-01	8.
327	6.786	-3.858E-03	8.006E-02	7.915E-02	183.0	1.22E+00	9.89E-01	4.
370	6.899	8.468E-02	7.704E-02	7.620E-02	-173.1	1.18E+00	9.89E-01	8.
330	6.922	2.079E-03	8.247E-02	8.065E-02	188.0	1.19E+00	9.78E-01	4.
333	7.242	-1.467E-03	7.643E-02	7.422E-02	188.0	1.17E+00	9.71E-01	3.
336	7.393	-2.114E-03	7.343E-02	7.092E-02	185.6	1.18E+00	9.66E-01	7.
339	7.468	-1.293E-03	7.196E-02	6.929E-02	-170.5	1.12E+00	9.63E-01	7.

Table 13 - 26 Kt Heave (Metric Units)

TWIN CUSHION SEV  
REGULAR WAVE DATA

JUNE 1976

HEAVE  
NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (METERS)	ROOTQ0 (METERS)	AMPLITUDE (METERS)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	1.323E-02	1.792E-03	3.759E-04	84.7	1.68E-02	2.10E-01	2.
346	1.495	6.868E-03	2.718E-03	2.110E-03	27.5	9.82E-02	7.76E-01	9.
349	1.741	2.677E-02	5.380E-03	3.505E-03	51.5	1.51E-01	6.51E-01	8.
304	2.222	2.252E-02	1.390E-02	1.268E-02	76.1	4.25E-01	9.12E-01	16.
352	2.263	2.043E-02	1.452E-02	1.190E-02	85.2	3.97E-01	8.19E-01	26.
307	2.930	2.637E-02	3.289E-02	3.061E-02	90.3	8.54E-01	9.31E-01	10.
310	3.813	1.956E-02	5.690E-02	5.634E-02	119.9	1.10E+00	9.90E-01	10.
313	4.341	1.748E-02	6.200E-02	6.086E-02	136.3	1.18E+00	9.81E-01	12.
316	5.001	1.205E-02	5.827E-02	5.568E-02	150.2	1.20E+00	9.56E-01	10.
319	5.930	1.009E-02	5.824E-02	5.232E-02	164.8	1.13E+00	8.99E-01	7.
355	6.272	2.357E+01	3.112E-02	3.002E-02	172.2	1.14E+00	9.65E-01	3.
358	6.326	6.568E-03	5.062E-02	4.915E-02	173.8	1.15E+00	9.71E-01	9.
361	6.387	1.151E-02	9.337E-02	9.177E-02	175.4	1.13E+00	9.83E-01	5.
322	6.393	1.991E-02	7.460E-02	6.614E-02	170.3	1.15E+00	8.87E-01	9.
364	6.433	2.949E-02	1.516E-01	1.470E-01	169.9	1.18E+00	9.70E-01	8.
328	6.757	-7.595E-03	8.166E-02	8.075E-02	176.7	1.16E+00	9.89E-01	17.
331	6.905	-1.259E-03	8.608E-02	8.222E-02	176.3	1.16E+00	9.55E-01	5.
334	7.175	-2.394E-03	5.479E-02	7.551E-02	-180.7	1.15E+00	9.75E-01	5.
337	7.242	-2.743E-03	7.737E-02	7.592E-02	179.3	1.15E+00	9.81E-01	5.
340	7.451	-3.124E-03	7.541E-02	7.229E-02	181.5	1.17E+00	9.59E-01	10.

Table 14 - 0 Kt Bow Acceleration (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

BOW ACCELERATION

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (G)	ROOTQ0 (G)	AMPLITUDE (G)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	3.276E-03	1.081E-01	6.219E-02	249.3	1.63E+00	5.75E-01	11.
344	1.499	-6.969E-04	1.258E-01	6.869E-02	237.4	1.66E+00	5.46E-01	4.
347	1.750	-2.347E-05	1.327E-01	7.365E-02	236.9	2.45E+00	5.55E-01	2.
302	2.290	3.452E-03	9.897E-02	4.771E-02	233.8	1.01E+00	4.82E-01	5.
350	2.360	-8.854E-04	1.197E-01	6.141E-02	220.7	1.79E+00	5.13E-01	5.
305	2.969	7.991E-03	9.650E-02	5.152E-02	226.9	1.44E+00	5.34E-01	6.
308	3.933	9.258E-03	1.006E-01	4.579E-02	221.2	1.28E+00	4.55E-01	6.
311	4.564	7.010E-03	9.033E-02	3.701E-02	210.4	1.12E-01	4.10E-01	5.
314	5.332	6.167E-03	1.012E-01	3.239E-02	195.3	1.44E+00	3.20E-01	4.
317	6.488	9.980E-03	1.038E-01	1.984E-02	191.4	8.75E-01	1.91E-01	6.
320	7.206	1.002E-02	8.853E-02	1.835E-02	208.2	7.69E-01	2.07E-01	4.
356	7.248	-2.214E-04	1.072E-01	1.217E-02	201.6	7.25E-01	1.14E-01	5.
359	7.272	3.311E-05	9.862E-02	3.112E-02	186.9	1.42E+00	3.16E-01	5.
362	7.291	-3.570E-05	1.068E-01	4.899E-02	-153.6	1.64E+00	4.59E-01	5.
353	7.333	-5.030E-04	9.430E-02	9.336E-03	-129.3	1.14E+00	9.90E-02	5.
365	7.433	-1.381E-03	1.416E-01	6.142E-02	193.2	1.50E+00	4.34E-01	5.
326	8.057	4.984E-03	1.075E-01	1.876E-02	199.8	9.09E-01	1.75E-01	1.
368	8.078	-1.534E-03	1.170E-01	1.984E-02	184.0	1.13E+00	1.70E-01	5.
329	8.253	5.898E-03	1.121E-01	2.433E-02	-157.6	1.54E+00	2.17E-01	3.
335	8.336	-1.964E-03	9.436E-02	1.988E-02	207.1	1.60E+00	2.11E-01	4.
332	8.553	7.228E-03	1.033E-01	1.962E-02	221.8	1.22E+00	1.90E-01	2.
338	8.881	-2.179E-03	9.888E-02	1.817E-02	193.2	1.70E+00	1.84E-01	1.

Table 15 - 20 Kt Bow Acceleration (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

BOW ACCELERATION

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (G)	ROOTQ0 (G)	AMPLITUDE (G)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	-1.177E-03	3.257E-01	2.908E-01	136.8	2.28E-01	8.93E-01	13.
301	1.506	3.759E-03	3.357E-01	3.038E-01	133.6	2.56E-01	9.05E-01	15.
342	1.530	6.296E-04	1.733E-01	1.080E-01	127.9	4.79E-01	6.23E-01	11.
348	1.737	4.813E-03	5.213E-01	4.848E-01	127.4	4.64E-01	9.30E-01	10.
351	2.243	-1.908E-03	6.486E-01	5.996E-01	134.4	6.74E-01	9.24E-01	8.
303	2.273	6.442E-03	6.056E-01	5.672E-01	126.0	6.93E-01	9.37E-01	18.
306	2.938	4.545E-03	7.909E-01	7.467E-01	138.1	1.14E+00	9.44E-01	12.
309	3.790	1.173E-02	9.009E-01	8.097E-01	153.7	1.44E+00	8.99E-01	4.
312	4.360	6.723E-03	7.333E-01	6.979E-01	161.2	1.66E+00	9.52E-01	12.
315	5.073	1.325E-02	5.477E-01	5.079E-01	175.6	1.82E+00	9.27E-01	5.
318	5.790	8.995E-03	3.978E-01	3.724E-01	192.2	1.60E+00	9.36E-01	12.
354	6.233	-6.675E-05	2.106E-01	1.362E-01	203.5	1.56E+00	6.47E-01	4.
366	6.260	-2.393E-02	1.014E+00	8.050E-01	183.6	1.33E+00	7.94E-01	3.
360	6.290	9.193E-03	4.591E-01	4.071E-01	206.1	1.39E+00	8.87E-01	3.
357	6.361	1.539E-03	2.958E-01	2.640E-01	202.7	1.64E+00	8.92E-01	5.
363	6.372	-8.530E-03	6.840E-01	6.045E-01	183.4	1.27E+00	8.84E-01	3.
321	6.397	1.093E-02	3.974E-01	3.634E-01	198.8	1.57E+00	9.15E-01	8.
327	6.786	4.603E-03	3.366E-01	3.089E-01	201.0	1.43E+00	9.18E-01	4.
370	6.899	-5.299E-03	3.679E-01	2.740E-01	-149.5	1.33E+00	7.45E-01	8.
330	6.922	3.340E-03	3.559E-01	2.994E-01	205.8	1.39E+00	8.41E-01	4.
333	7.242	6.649E-03	3.069E-01	2.498E-01	208.1	1.39E+00	8.14E-01	3.
336	7.393	3.753E-03	2.749E-01	2.294E-01	207.2	1.40E+00	8.35E-01	7.
339	7.468	-5.557E-04	2.573E-01	2.154E-01	-147.9	1.30E+00	8.37E-01	7.

Table 16 - 26 Kt Bow Acceleration (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

BOW ACCELERATION

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (G)	ROOTQ0 (G)	AMPLITUDE (G)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	6.502E-03	3.748E-01	3.336E-01	222.4	1.06E-01	8.90E-01	2.
346	1.495	-4.212E-04	3.115E-01	2.853E-01	146.9	1.40E-01	9.16E-01	9.
349	1.741	2.946E-03	3.883E-01	3.517E-01	132.3	2.12E-01	9.06E-01	8.
304	2.222	2.384E-03	6.908E-01	6.291E-01	127.4	4.62E-01	9.11E-01	16.
352	2.263	-4.482E-03	7.306E-01	6.383E-01	136.8	4.82E-01	8.74E-01	26.
307	2.930	6.993E-03	8.059E-01	7.080E-01	121.1	7.23E-01	8.79E-01	10.
310	3.813	7.077E-03	9.450E-01	7.892E-01	139.6	9.34E-01	8.35E-01	10.
313	4.341	6.883E-01	2.441E+00	6.887E-01	149.1	1.04E+00	8.96E-01	12.
316	5.001	2.660E-03	5.784E-01	5.208E-01	158.8	1.16E+00	9.00E-01	10.
319	5.930	1.264E-02	4.414E-01	3.811E-01	172.1	1.25E+00	8.63E-01	7.
355	6.272	-2.497E-03	2.230E-01	1.816E-01	-177.1	1.19E+00	8.14E-01	3.
358	6.326	-4.206E-05	3.166E-01	2.883E-01	182.6	1.18E+00	9.11E-01	9.
361	6.387	3.378E-03	5.345E-01	4.903E-01	-175.3	1.09E+00	9.17E-01	5.
322	6.393	1.373E-02	4.406E-01	3.724E-01	179.3	1.19E+00	8.45E-01	9.
364	6.433	-4.779E-04	8.852E-01	7.482E-01	177.0	1.10E+00	8.45E-01	8.
328	6.757	4.651E-03	4.417E-01	4.046E-01	183.0	1.20E+00	9.16E-01	17.
331	6.905	5.949E-03	4.503E-01	3.969E-01	178.8	1.22E+00	8.81E-01	5.
334	7.175	1.788E-03	3.704E-01	3.373E-01	-174.1	1.23E+00	9.11E-01	5.
337	7.242	-6.126E-04	3.827E-01	3.391E-01	186.1	1.26E+00	8.86E-01	5.
340	7.451	-2.105E-03	3.471E-01	3.058E-01	191.1	1.29E+00	8.81E-01	10.

Table 17 - 0 Kt Relative Bow Motion (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

RELATIVE BOW MOTION

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (METERS)	ROOTQ0 (METERS)	AMPLITUDE (METERS)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	-3.071E-03	4.890E-02	3.894E-03	186.8	9.57E-01	3.91E-01	11.
344	1.499	-9.637E-03	1.049E-01	5.552E-02	220.4	2.59E+00	5.29E-01	4.
347	1.750	1.725E-02	8.242E-02	5.870E-02	201.6	3.23E+00	7.12E-01	2.
302	2.290	2.421E-02	5.565E-02	2.591E-02	170.8	6.91E-01	4.66E-01	5.
350	2.360	1.274E-02	6.500E-02	4.234E-02	193.7	1.52E+00	6.51E-01	5.
305	2.969	1.129E-02	4.056E-02	2.363E-02	170.5	6.40E-01	5.83E-01	6.
308	3.933	-1.262E-01	2.279E-01	7.178E-02	110.0	1.44E+00	3.15E-01	6.
311	4.564	-7.752E-02	2.041E-01	7.892E-02	135.0	1.46E+00	3.87E-01	5.
314	5.332	-9.289E-02	2.244E-01	5.278E-02	167.6	1.18E+00	2.35E-01	4.
317	6.488	-9.418E-02	2.267E-01	5.941E-02	158.7	1.03E+00	2.62E-01	6.
320	7.206	-1.566E-02	1.446E-01	1.089E-02	232.8	1.54E-01	7.54E-02	4.
356	7.248	-1.149E-03	7.414E-02	1.332E-02	167.3	2.65E-01	1.80E-01	5.
359	7.272	5.446E-03	4.590E-02	1.691E-02	185.9	2.57E-01	3.68E-01	5.
362	7.291	7.437E-03	4.011E-02	2.555E-02	-174.4	2.83E-01	6.37E-01	5.
353	7.333	-4.018E-03	9.510E-02	2.697E-03	-116.0	1.09E-01	2.84E-02	5.
365	7.433	-2.771E-03	5.692E-02	3.592E-02	168.2	2.84E-01	6.31E-01	5.
326	8.057	-2.053E-03	7.407E-02	1.171E-02	276.3	1.62E-01	1.58E-01	1.
368	8.078	-1.023E-03	7.064E-02	1.364E-02	141.7	2.22E-01	1.93E-01	5.
329	8.253	4.366E-03	3.919E-02	1.422E-02	-165.7	2.49E-01	3.63E-01	3.
335	8.336	4.663E-03	4.524E-02	6.800E-03	219.2	1.49E-01	1.50E-01	4.
332	8.553	-1.214E-02	8.816E-02	2.228E-02	184.5	3.63E-01	2.53E-01	2.
338	8.881	1.478E-03	5.123E-02	7.920E-03	234.8	1.84E-01	1.55E-01	1.

Table 18 - 20 Kt Relative Bow Motion (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

RELATIVE BOW MOTION

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (METERS)	ROOTQ0 (METERS)	AMPLITUDE (METERS)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	-8.931E-03	2.654E-02	2.491E-02	150.6	1.20E+00	9.39E-01	13.
342	1.530	-1.498E-02	8.476E-03	6.190E-03	136.6	1.61E+00	7.30E-01	11.
301	1.560	1.280E-02	2.746E-02	2.417E-02	128.3	1.23E+00	8.80E-01	15.
348	1.757	6.683E-03	3.993E-02	3.383E-02	129.9	1.47E+00	8.47E-01	10.
351	2.243	1.284E-02	5.563E-02	5.014E-02	115.0	1.66E+00	9.01E-01	8.
303	2.273	1.678E-02	6.063E-02	3.467E-02	116.2	1.21E+00	5.72E-01	18.
306	2.938	2.677E-02	7.376E-02	4.864E-02	112.9	1.33E+00	6.60E-01	12.
309	3.790	-3.096E-02	1.526E-01	1.140E-01	115.1	2.27E+00	7.47E-01	4.
312	4.360	-2.286E-02	1.663E-01	1.271E-01	129.2	2.58E+00	7.64E-01	12.
315	5.073	-7.859E-02	2.171E-01	1.512E-01	140.7	3.40E+00	6.96E-01	5.
318	5.790	-4.849E-02	1.634E-01	9.533E-02	160.3	1.95E+00	5.84E-01	12.
354	6.233	-4.994E-03	2.149E-02	1.890E-02	175.1	8.80E-01	8.80E-01	4.
366	6.260	5.298E-03	1.857E-01	1.713E-01	131.2	1.13E+00	9.23E-01	3.
360	6.290	-4.300E-03	6.304E-02	5.959E-02	171.2	8.09E-01	9.45E-01	3.
357	6.361	-8.527E-03	3.813E-02	3.686E-02	172.2	8.86E-01	9.67E-01	5.
363	6.372	-2.483E-03	1.122E-01	1.044E-01	136.7	8.44E-01	9.30E-01	3.
321	6.397	-4.216E-02	1.530E-01	9.746E-02	146.9	1.61E+00	6.37E-01	8.
327	6.786	-3.259E-02	4.547E-02	4.384E-02	166.6	6.73E-01	9.64E-01	4.
370	6.899	1.479E-01	3.495E-02	3.045E-02	-172.8	4.73E-01	8.71E-01	8.
330	6.922	-2.865E-02	4.552E-02	4.247E-02	175.3	6.24E-01	9.33E-01	4.
333	7.242	-2.901E-02	3.884E-02	3.663E-02	180.7	5.78E-01	9.43E-01	3.
336	7.393	-3.198E-02	3.315E-02	3.101E-02	181.1	5.18E-01	9.35E-01	7.
339	7.468	-3.200E-02	3.028E-02	2.809E-02	-170.6	4.53E-01	9.27E-01	7.

Table 19 - 26 Kt Relative Bow Motion (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

RELATIVE BOW MOTION

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (METERS)	ROOTQ0 (METERS)	AMPLITUDE (METERS)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	2.112E-02	2.703E-02	2.616E-02	195.1	1.17E+00	9.68E-01	2.
346	1.495	7.953E-03	2.486E-02	2.444E-02	150.2	1.14E+00	9.83E-01	9.
349	1.741	6.993E-02	3.035E-02	2.888E-02	128.7	1.25E+00	9.51E-01	8.
304	2.222	3.825E-02	4.506E-02	4.369E-02	107.7	1.47E+00	9.70E-01	16.
352	2.263	4.844E-02	4.788E-02	4.382E-02	113.3	1.46E+00	9.15E-01	26.
307	2.930	5.141E-02	6.053E-02	5.784E-02	91.6	1.61E+00	9.56E-01	10.
310	3.813	4.729E-02	8.291E-02	8.062E-02	95.3	1.58E+00	9.73E-01	10.
313	4.341	2.863E-02	9.688E-02	8.077E-02	100.1	1.56E+00	8.34E-01	12.
316	5.001	-3.355E-02	1.786E-01	1.010E-01	103.8	2.17E+00	5.65E-01	10.
319	5.930	-6.993E-02	1.999E-01	9.350E-02	102.5	2.02E+00	4.68E-01	7.
355	6.272	1.634E-02	2.318E-02	2.146E-02	124.4	8.18E-01	9.25E-01	3.
358	6.326	1.352E-02	4.044E-02	3.688E-02	125.2	8.60E-01	9.13E-01	9.
361	6.387	2.738E-02	6.520E-02	6.388E-02	126.1	7.89E-01	9.80E-01	5.
322	6.393	8.870E-03	1.046E-01	6.271E-02	103.8	1.09E+00	5.99E-01	9.
364	6.433	6.434E-02	1.182E-01	1.115E-01	116.2	8.98E-01	9.44E-01	8.
328	6.757	-1.642E-02	6.027E-02	5.840E-02	127.3	8.46E-01	9.75E-01	17.
331	6.905	-9.794E-03	6.967E-02	6.472E-02	124.3	9.17E-01	9.29E-01	5.
334	7.175	-1.431E-02	4.854E-02	4.696E-02	-224.5	7.14E-01	9.67E-01	5.
337	7.242	-2.213E-02	5.319E-02	5.146E-02	136.6	7.78E-01	9.68E-01	5.
340	7.451	-1.532E-02	4.666E-02	4.379E-02	140.9	7.09E-01	9.38E-01	10.

Table 20 - 0 Kt Average Cushion Pressure (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AVERAGE CUSHION PRESSURE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PASCAL)	ROOTQ0 (PASCAL)	AMPLITUDE (PASCAL)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	3.964E+02	2.837E+01	5.020E+00	186.4	3.98E+00	1.77E-01	11.
344	1.499	3.933E+02	2.964E+01	2.876E+00	148.9	2.12E+00	9.70E-02	4.
347	1.750	4.004E+02	3.530E+01	3.420E+00	169.9	2.98E+00	9.69E-02	2.
302	2.290	3.965E+02	3.039E+01	5.998E+00	171.1	2.53E+00	1.97E-01	5.
350	2.360	4.139E+02	3.130E+01	8.363E+00	153.7	4.75E+00	2.67E-01	5.
305	2.969	4.098E+02	2.860E+01	1.011E+01	165.1	4.34E+00	3.54E-01	6.
308	3.933	4.121E+02	3.253E+01	6.950E+00	157.5	2.21E+00	2.14E-01	6.
311	4.564	4.143E+02	3.241E+01	1.167E+01	156.9	3.42E+00	3.60E-01	5.
314	5.332	4.102E+02	3.705E+01	7.108E+00	135.6	2.53E+00	1.92E-01	4.
317	6.488	3.923E+02	4.045E+01	7.246E+00	137.5	1.99E+00	1.79E-01	6.
320	7.206	4.198E+02	3.723E+01	7.632E+00	142.6	1.71E+00	2.05E-01	4.
356	7.248	3.904E+02	3.902E+01	4.641E+00	116.4	1.46E+00	1.19E-01	5.
359	7.272	4.221E+02	3.490E+01	1.011E+01	151.5	2.43E+00	2.90E-01	5.
362	7.291	4.397E+02	3.400E+01	1.423E+01	-182.7	2.50E+00	4.19E-01	5.
353	7.333	4.042E+02	3.263E+01	2.499E+00	136.5	1.60E+00	7.66E-02	5.
365	7.433	4.135E+02	3.927E+01	1.997E+01	165.1	2.50E+00	5.08E-01	5.
326	8.057	3.977E+02	3.542E+01	5.616E+00	148.9	1.23E+00	1.59E-01	1.
368	8.078	4.017E+02	3.403E+01	7.405E+00	136.3	1.91E+00	2.18E-01	5.
329	8.253	3.825E+02	3.523E+01	7.839E+00	-199.1	2.17E+00	2.23E-01	3.
335	8.336	4.100E+02	3.100E+01	6.943E+00	165.0	2.41E+00	2.24E-01	4.
332	8.553	4.055E+02	3.332E+01	6.489E+00	180.3	1.67E+00	1.95E-01	2.
338	8.881	3.920E+02	3.283E+01	5.724E+00	172.4	2.11E+00	1.74E-01	1.

Table 21 - 20 Kt Average Cushion Pressure (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AVERAGE CUSHION PRESSURE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PASCAL)	ROOTQ0 (PASCAL)	AMPLITUDE (PASCAL)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	3.150E+02	1.208E+02	1.143E+02	63.4	8.71E+01	9.47E-01	13.
301	1.506	3.192E+02	1.070E+02	1.030E+02	54.6	8.28E+01	9.62E-01	15.
342	1.530	2.935E+02	4.574E+01	3.025E+01	89.8	1.25E+02	6.61E-01	11.
348	1.757	3.552E+02	1.802E+02	1.675E+02	76.7	1.15E+02	9.30E-01	10.
351	2.243	3.417E+02	2.257E+02	2.146E+02	91.1	1.12E+02	9.50E-01	8.
303	2.273	3.212E+02	2.187E+02	2.107E+02	86.4	1.17E+02	9.63E-01	18.
306	2.938	3.297E+02	2.710E+02	2.611E+02	108.0	1.13E+02	9.64E-01	12.
309	3.790	3.261E+02	2.836E+02	2.677E+02	129.9	8.44E+01	9.44E-01	4.
312	4.360	3.444E+02	2.430E+02	2.327E+02	139.7	7.48E+01	9.58E-01	12.
315	5.073	3.348E+02	1.684E+02	1.601E+02	151.0	5.71E+01	9.51E-01	5.
318	5.790	3.236E+02	1.223E+02	1.168E+02	168.8	3.79E+01	9.55E-01	12.
354	6.233	3.411E+02	5.990E+01	4.117E+01	174.7	3.04E+01	6.87E-01	4.
366	6.260	3.208E+02	3.980E+02	3.020E+02	166.2	3.17E+01	7.59E-01	3.
360	6.290	3.538E+02	1.460E+02	1.313E+02	180.9	2.83E+01	9.00E-01	3.
357	6.361	3.297E+02	8.970E+01	8.246E+01	175.7	3.14E+01	9.20E-01	5.
363	6.372	3.396E+02	2.359E+02	2.100E+02	164.2	2.69E+01	8.90E-01	3.
321	6.397	3.383E+02	1.244E+02	1.158E+02	172.3	3.03E+01	9.31E-01	8.
327	6.786	3.193E+02	1.105E+02	1.049E+02	177.1	2.55E+01	9.50E-01	4.
370	6.899	3.569E+02	9.722E+01	7.894E+01	-178.7	1.94E+01	8.12E-01	8.
330	6.922	2.954E+02	1.167E+02	1.020E+02	180.9	2.37E+01	8.73E-01	4.
333	7.242	3.336E+02	9.694E+01	8.377E+01	181.9	2.10E+01	8.64E-01	3.
336	7.393	3.257E+02	8.687E+01	7.770E+01	179.6	2.05E+01	8.94E-01	7.
339	7.468	3.098E+02	7.977E+01	7.053E+01	-176.0	1.80E+01	8.84E-01	7.

Table 22 - 26 Kt Average Cushion Pressure (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AVERAGE CUSHION PRESSURE

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PASCAL)	ROOTQ0 (PASCAL)	AMPLITUDE (PASCAL)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLE
343	1.213	2.554E+02	9.129E+01	7.874E+01	301.4	5.58E+01	8.62E-01	2.
346	1.495	2.828E+02	1.236E+02	1.140E+02	39.3	8.41E+01	9.23E-01	9.
349	1.741	3.272E+02	1.502E+02	1.361E+02	47.3	9.30E+01	9.06E-01	8.
304	2.222	3.061E+02	2.621E+02	2.490E+02	67.1	1.32E+02	9.50E-01	16.
352	2.263	3.245E+02	2.543E+02	2.299E+02	75.4	1.21E+02	9.04E-01	26.
307	2.930	3.172E+02	3.729E+02	3.387E+02	81.8	1.50E+02	9.08E-01	10.
310	3.813	3.142E+02	3.929E+02	3.476E+02	110.2	1.08E+02	8.85E-01	10.
313	4.341	3.216E+02	3.298E+02	3.042E+02	126.6	9.34E+01	9.22E-01	12.
316	5.001	3.003E+02	2.249E+02	2.110E+02	140.0	7.18E+01	9.38E-01	10.
319	5.930	2.939E+02	1.660E+02	1.464E+02	151.7	5.01E+01	8.82E-01	7.
355	6.272	3.052E+02	8.232E+01	7.295E+01	158.8	4.41E+01	8.86E-01	3.
358	6.326	2.976E+02	1.187E+02	1.124E+02	160.8	4.15E+01	9.47E-01	9.
361	6.387	3.296E+02	2.143E+02	1.986E+02	164.4	3.89E+01	9.27E-01	5.
322	6.393	3.213E+02	1.717E+02	1.482E+02	158.2	4.08E+01	8.63E-01	9.
364	6.433	3.490E+02	3.489E+02	2.976E+02	155.3	3.80E+01	8.53E-01	8.
328	6.757	2.885E+02	1.714E+02	1.591E+02	163.7	3.63E+01	9.28E-01	17.
331	6.905	2.683E+02	1.748E+02	1.554E+02	160.9	3.49E+01	8.89E-01	5.
334	7.175	2.932E+02	1.397E+02	1.308E+02	-194.9	3.15E+01	9.36E-01	5.
337	7.242	2.911E+02	1.391E+02	1.270E+02	165.6	3.04E+01	9.13E-01	5.
340	7.451	2.756E+02	1.298E+02	1.174E+02	168.2	3.01E+01	9.05E-01	10.

Table 23 - 0 Kt Forward Cushion Pressure (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

FORWARD CUSHION PRESSURE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PASCAL)	ROOTQ0 (PASCAL)	AMPLITUDE (PASCAL)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	4.571E+02	3.411E+01	2.207E+01	185.2	1.75E+01	6.47E-01	11.
344	1.499	4.840E+02	3.170E+01	1.625E+01	214.0	1.20E+01	5.12E-01	4.
347	1.750	4.642E+02	3.922E+01	1.859E+01	204.6	1.62E+01	4.74E-01	2.
302	2.290	4.839E+02	3.502E+01	1.973E+01	182.2	8.34E+00	5.63E-01	5.
350	2.360	4.675E+02	3.322E+01	2.045E+01	177.6	1.16E+01	6.16E-01	5.
305	2.969	4.764E+02	3.520E+01	2.570E+01	187.8	1.01E+01	7.30E-01	6.
308	3.933	4.933E+02	3.344E+01	1.777E+01	178.4	5.66E+00	5.31E-01	6.
311	4.564	4.598E+02	3.736E+01	2.176E+01	173.5	3.42E+00	3.60E-01	5.
314	5.332	4.526E+02	3.758E+01	1.475E+01	162.9	5.24E+00	3.92E-01	4.
317	6.488	4.625E+02	4.128E+01	1.270E+01	154.7	3.48E+00	3.08E-01	6.
320	7.206	4.755E+02	3.693E+01	1.245E+01	170.8	2.78E+00	3.37E-01	4.
356	7.248	4.589E+02	3.574E+01	6.838E+00	146.5	2.15E+00	1.91E-01	5.
359	7.272	4.836E+02	3.580E+01	1.844E+01	159.7	4.43E+00	5.15E-01	5.
362	7.291	5.019E+02	3.649E+01	2.177E+01	-173.6	3.83E+00	5.97E-01	5.
353	7.333	4.615E+02	2.671E+01	4.960E+00	162.1	3.18E+00	1.86E-01	5.
365	7.433	5.089E+02	5.730E+01	4.044E+01	174.2	5.06E+00	7.06E-01	5.
326	8.057	4.758E+02	3.808E+01	1.005E+01	163.1	2.21E+00	2.64E-01	1.
368	8.078	4.942E+02	3.305E+01	1.218E+01	153.0	3.15E+00	3.68E-01	5.
329	8.253	4.969E+02	3.584E+01	9.625E+00	-203.6	2.67E+00	2.44E-01	3.
335	8.336	4.865E+02	2.985E+01	1.285E+01	174.6	4.46E+00	4.30E-01	4.
332	8.553	4.856E+02	2.906E+01	1.196E+01	191.3	3.09E+00	4.12E-01	2.
338	8.881	5.075E+02	3.252E+01	7.439E+00	171.5	2.74E+00	2.29E-01	1.

Table 24 - 20 Kt Forward Cushion Pressure (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

FORWARD CUSHION PRESSURE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PASCAL)	ROOTQ0 (PASCAL)	AMPLITUDE (PASCAL)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	3.913E+02	1.344E+02	1.262E+02	86.7	9.61E+01	9.39E-01	13.
301	1.506	3.909E+02	1.565E+02	1.397E+02	77.7	1.12E+02	8.92E-01	15.
342	1.530	4.041E+02	6.624E+01	4.691E+01	96.6	1.93E+02	7.08E-01	11.
348	1.757	4.078E+02	2.284E+02	2.145E+02	85.5	1.48E+02	9.39E-01	10.
351	2.243	3.971E+02	3.047E+02	2.882E+02	96.5	1.51E+02	9.46E-01	8.
303	2.273	3.701E+02	3.040E+02	2.831E+02	93.9	1.57E+02	9.31E-01	18.
306	2.938	3.889E+02	3.809E+02	3.638E+02	110.7	1.58E+02	9.55E-01	12.
309	3.790	3.654E+02	3.968E+02	3.786E+02	128.0	1.19E+02	9.54E-01	4.
312	4.360	3.949E+02	3.552E+02	3.451E+02	138.4	1.11E+02	9.72E-01	12.
315	5.073	3.922E+02	2.569E+02	2.474E+02	151.9	8.83E+01	9.63E-01	5.
318	5.790	3.829E+02	1.944E+02	1.878E+02	169.8	6.09E+01	9.66E-01	12.
354	6.233	4.157E+02	8.770E+01	6.643E+01	180.7	4.90E+01	7.58E-01	4.
366	6.260	3.774E+02	4.763E+02	4.069E+02	164.1	4.27E+01	8.54E-01	3.
360	6.290	4.186E+02	2.117E+02	1.923E+02	186.5	4.14E+01	9.08E-01	3.
357	6.361	4.053E+02	1.376E+02	1.301E+02	181.0	4.96E+01	9.46E-01	5.
363	6.372	3.720E+02	3.267E+02	3.019E+02	161.4	3.87E+01	9.24E-01	3.
321	6.397	3.897E+02	1.917E+02	1.811E+02	175.7	4.75E+01	9.45E-01	8.
327	6.786	4.011E+02	1.640E+02	1.587E+02	182.2	3.86E+01	9.68E-01	4.
370	6.899	4.699E+02	1.434E+02	1.173E+02	-172.7	2.89E+01	8.18E-01	8.
330	6.922	3.920E+02	1.715E+02	1.500E+02	186.8	3.49E+01	8.75E-01	4.
333	7.242	4.107E+02	1.439E+02	1.258E+02	187.5	3.15E+01	8.74E-01	3.
336	7.393	4.049E+02	1.309E+02	1.188E+02	185.7	3.14E+01	9.07E-01	7.
339	7.468	4.123E+02	1.129E+02	1.020E+02	-168.8	2.61E+01	9.05E-01	7.

Table 25 - 26 Kt Forward Cushion Pressure (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

FORWARD CUSHION PRESSURE

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PASCAL)	ROOTQ0 (PASCAL)	AMPLITUDE (PASCAL)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	3.732E+02	2.072E+02	2.046E+02	196.3	1.45E+02	9.88E-01	2.
346	1.495	3.587E+02	1.027E+02	9.404E+01	89.9	6.93E+01	9.15E-01	9.
349	1.741	3.981E+02	1.351E+02	1.269E+02	74.3	8.67E+01	9.39E-01	8.
304	2.222	3.728E+02	4.733E+02	4.548E+02	115.9	2.42E+02	9.61E-01	16.
352	2.263	3.239E+02	3.560E+02	3.066E+02	104.8	1.62E+02	8.61E-01	26.
307	2.930	3.061E+02	3.551E+02	3.132E+02	92.0	1.38E+02	8.82E-01	10.
310	3.813	3.472E+02	4.629E+02	4.144E+02	105.8	1.29E+02	8.95E-01	10.
313	4.341	3.625E+02	4.110E+02	3.805E+02	119.4	1.17E+02	9.26E-01	12.
316	5.001	3.448E+02	3.099E+02	2.899E+02	133.0	9.86E+01	9.36E-01	10.
319	5.930	3.487E+02	2.390E+02	2.133E+02	145.9	7.30E+01	8.92E-01	7.
355	6.272	3.793E+02	1.163E+02	1.068E+02	155.2	6.45E+01	9.18E-01	3.
358	6.326	3.774E+02	1.731E+02	1.659E+02	157.8	6.13E+01	9.58E-01	9.
361	6.387	3.976E+02	2.877E+02	2.729E+02	161.8	5.34E+01	9.49E-01	5.
322	6.393	3.781E+02	2.419E+02	2.110E+02	154.0	5.81E+01	8.72E-01	9.
364	6.433	3.859E+02	4.284E+02	3.861E+02	150.1	4.93E+01	9.01E-01	8.
328	6.757	3.657E+02	2.370E+02	2.221E+02	162.3	5.06E+01	9.37E-01	17.
331	6.905	3.600E+02	2.471E+02	2.259E+02	156.6	5.07E+01	9.14E-01	5.
334	7.175	3.634E+02	1.984E+02	1.866E+02	-195.0	4.50E+01	9.41E-01	5.
337	7.242	3.598E+02	2.002E+02	1.846E+02	165.5	4.43E+01	9.22E-01	5.
340	7.451	3.667E+02	1.783E+02	1.627E+02	170.4	4.18E+01	9.13E-01	10.

Table 26 - 0 Kt Aft Cushion Pressure (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AFT CUSHION PRESSURE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PASCAL)	ROOTQ0 (PASCAL)	AMPLITUDE (PASCAL)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	4.017E+02	3.192E+01	1.502E+01	160.7	1.19E+01	4.70E-01	11.
344	1.499	3.895E+02	3.501E+01	1.454E+01	142.3	1.07E+01	4.15E-01	4.
347	1.750	3.720E+02	3.386E+01	1.072E+01	154.3	9.33E+00	3.17E-01	2.
302	2.290	4.013E+02	3.312E+01	1.346E+01	163.5	5.69E+00	4.06E-01	5.
350	2.360	3.854E+02	3.516E+01	2.533E+04	79.7	1.97E+00	7.44E-01	5.
305	2.969	3.992E+02	3.361E+01	1.622E+01	137.6	6.97E+00	4.83E-01	6.
308	3.933	3.845E+02	3.912E+01	1.619E+01	156.7	5.16E+00	4.14E-01	6.
311	4.564	3.887E+02	3.738E+01	1.975E+01	151.3	5.79E+00	5.28E-01	5.
314	5.332	3.971E+02	3.611E+01	1.116E+01	131.4	3.96E+00	3.09E-01	4.
317	6.408	3.652E+02	4.299E+01	1.270E+01	154.7	3.48E+00	3.08E-01	6.
320	7.206	3.856E+02	3.603E+01	1.035E+01	142.3	2.31E+00	2.87E-01	4.
356	7.248	3.624E+02	3.894E+01	5.019E+00	119.2	1.58E+00	1.29E-01	5.
359	7.272	3.993E+02	3.511E+01	1.506E+01	145.4	3.62E+00	4.29E-01	5.
362	7.291	3.947E+02	3.827E+01	1.949E+01	-188.4	3.42E+00	5.09E-01	5.
353	7.333	3.893E+02	3.047E+01	3.978E+00	137.8	2.55E+00	1.31E-01	5.
365	7.433	3.645E+02	4.284E+01	2.401E+01	159.5	3.00E+00	5.60E-01	5.
326	8.057	3.885E+02	3.842E+01	7.819E+00	147.5	1.72E+00	2.03E-01	1.
368	8.078	3.536E+02	3.749E+01	9.542E+00	134.2	2.47E+00	2.55E-01	5.
329	8.253	3.821E+02	3.944E+01	9.625E+00	-203.6	2.67E+00	2.44E-01	3.
335	8.336	3.859E+02	3.364E+01	7.626E+00	165.9	2.64E+00	2.27E-01	4.
332	8.553	3.820E+02	3.478E+01	6.525E+00	168.4	1.68E+00	1.88E-01	2.
338	8.881	4.015E+02	3.547E+01	7.143E+00	149.0	2.63E+00	2.01E-01	1.

Table 27 - 20 Kt Aft Cushion Pressure (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AFT CUSHION PRESSURE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PASCAL)	ROOTQ0 (PASCAL)	AMPLITUDE (PASCAL)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	3.199E+02	1.725E+02	1.663E+02	20.6	1.27E+02	9.64E-01	13.
301	1.506	2.981E+02	1.787E+02	1.633E+02	12.2	1.31E+02	9.14E-01	15.
342	1.530	3.090E+02	4.569E+01	3.033E+01	49.7	1.25E+02	6.64E-01	11.
348	1.757	3.320E+02	2.166E+02	2.044E+02	44.0	1.41E+02	9.44E-01	10.
351	2.243	3.130E+02	2.417E+02	2.316E+02	63.5	1.21E+02	9.58E-01	8.
303	2.273	2.927E+02	2.268E+02	2.092E+02	61.6	1.16E+02	9.22E-01	18.
306	2.938	3.178E+02	2.765E+02	2.648E+02	90.7	1.15E+02	9.58E-01	12.
309	3.790	3.027E+02	2.742E+02	2.630E+02	117.1	8.29E+01	9.59E-01	4.
312	4.360	3.243E+02	2.219E+02	2.126E+02	129.3	6.83E+01	9.57E-01	12.
315	5.073	3.070E+02	1.535E+02	1.471E+02	138.9	5.25E+01	5.27E-01	5.
318	5.790	3.101E+02	1.098E+02	1.049E+02	157.3	3.40E+01	9.56E-01	12.
354	6.233	3.197E+02	5.336E+01	3.688E+01	159.9	2.72E+01	6.91E-01	4.
366	6.260	2.765E+02	3.701E+02	2.874E+02	161.7	3.02E+01	7.77E-01	3.
360	6.290	3.253E+02	1.362E+02	1.213E+02	168.2	2.61E+01	8.91E-01	3.
357	6.361	3.258E+02	8.191E+01	7.529E+01	161.6	2.87E+01	9.19E-01	5.
363	6.372	2.785E+02	2.314E+02	1.970E+02	159.3	2.53E+01	8.51E-01	3.
321	6.397	3.147E+02	1.158E+02	1.081E+02	159.2	2.83E+01	9.34E-01	8.
327	6.789	3.065E+02	1.091E+02	1.020E+02	164.0	2.48E+01	9.34E-01	4.
370	6.899	3.087E+02	1.005E+02	8.356E+01	-191.8	2.06E+01	8.31E-01	8.
330	6.922	3.085E+02	1.086E+02	9.694E+01	167.7	2.26E+01	8.93E-01	4.
333	7.242	3.255E+02	9.087E+01	7.832E+01	168.2	1.96E+01	8.62E-01	3.
336	7.393	2.912E+02	8.115E+01	7.329E+01	165.9	1.94E+01	9.03E-01	7.
339	7.468	3.226E+02	7.998E+01	7.191E+01	-191.4	1.84E+01	8.99E-01	7.

Table 28 - 26 Kt Aft Cushion Pressure (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AFT CUSHION PRESSURE

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PASCAL)	ROOTQ0 (PASCAL)	AMPLITUDE (PASCAL)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	2.597E+02	2.130E+02	2.092E+02	304.0	1.48E+02	9.82E-01	2.
346	1.495	2.817E+02	2.297E+02	2.259E+02	349.8	1.67E+02	9.83E-01	9.
349	1.741	2.825E+02	2.305E+02	2.191E+02	2.1	1.50E+02	9.51E-01	8.
304	2.222	2.945E+02	3.281E+02	3.010E+02	95.4	1.60E+02	9.17E-01	16.
352	2.263	2.219E+02	2.897E+02	2.283E+02	63.2	1.21E+02	7.88E-01	26.
307	2.930	2.140E+02	3.128E+02	2.802E+02	62.0	1.24E+02	8.96E-01	10.
310	3.813	2.623E+02	4.224E+02	3.819E+02	95.4	1.19E+02	9.04E-01	10.
313	4.341	2.856E+02	3.486E+02	3.215E+02	116.7	9.87E+01	9.22E-01	12.
316	5.001	2.703E+02	2.289E+02	2.160E+02	133.2	7.35E+01	9.44E-01	10.
319	5.930	2.761E+02	1.651E+02	1.462E+02	145.5	5.01E+01	8.86E-01	7.
355	6.272	2.761E+02	7.901E+01	6.936E+01	153.9	4.19E+01	8.78E-01	3.
358	6.326	2.800E+02	1.133E+02	1.060E+02	155.6	3.91E+01	9.36E-01	9.
361	6.387	2.872E+02	2.193E+02	2.020E+02	159.4	3.95E+01	9.22E-01	5.
322	6.393	2.918E+02	1.740E+02	1.481E+02	152.8	4.08E+01	8.51E-01	9.
364	6.433	2.583E+02	3.581E+02	3.043E+02	150.6	3.88E+01	8.50E-01	8.
328	6.757	2.771E+02	1.662E+02	1.521E+02	159.0	3.47E+01	9.15E-01	17.
331	6.905	2.803E+02	1.684E+02	1.446E+02	158.2	3.25E+01	8.58E-01	5.
334	7.175	2.852E+02	1.347E+02	1.243E+02	-200.6	2.99E+01	9.23E-01	5.
337	7.242	2.627E+02	1.285E+02	1.162E+02	159.0	2.79E+01	9.05E-01	5.
340	7.451	2.861E+02	1.241E+02	1.108E+02	160.9	2.84E+01	8.93E-01	10.

Table 29 - 0 Kt Drag (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

DRAG

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (NEWTON)	ROOTQ0 (NEWTON)	AMPLITUDE (NEWTON)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	1.910E+00	1.147E+01	8.434E+00	118.8	1.42E+00	7.35E-01	11.
344	1.499	3.943E+00	9.773E+00	9.065E+00	111.5	1.42E+00	9.28E-01	4.
347	1.750	8.145E-01	1.472E+01	1.282E+01	104.1	2.37E+00	8.71E-01	2.
302	2.290	2.310E+00	1.672E+01	1.278E+01	106.3	1.15E+00	7.64E-01	5.
350	2.360	2.581E+00	2.196E+01	1.634E+01	79.7	1.97E+00	7.44E-01	5.
305	2.969	4.349E+00	2.193E+01	1.181E+00	184.2	1.61E+00	8.07E-01	6.
308	3.933	1.835E+00	2.218E+01	1.902E+01	96.0	1.29E+00	8.58E-01	6.
311	4.564	3.699E+00	2.164E+01	1.758E+01	90.5	1.09E+00	8.12E-01	5.
314	5.332	4.329E+00	1.645E+01	1.518E+01	59.4	1.15E+00	9.23E-01	4.
317	6.488	3.432E+00	1.491E+01	1.436E+01	84.8	8.36E-01	9.63E-01	6.
320	7.206	3.956E+00	2.213E+01	2.025E+01	87.0	9.61E-01	9.15E-01	4.
356	7.248	8.345E-01	1.432E+01	1.378E+01	87.8	9.21E-01	9.62E-01	5.
359	7.272	1.690E+00	2.017E+01	1.770E+01	68.5	9.03E-01	8.78E-01	5.
362	7.291	1.645E-01	3.663E+01	3.047E+01	71.2	1.14E+00	8.32E-01	5.
353	7.333	1.603E+00	9.759E+00	8.745E+00	86.0	1.19E+00	8.96E-01	5.
365	7.433	-1.478E+00	4.060E+01	3.565E+01	66.9	9.47E-01	8.78E-01	5.
326	8.057	4.362E+00	2.124E+01	1.833E+01	82.3	8.55E-01	8.63E-01	1.
368	8.078	-1.838E+00	1.779E+01	1.496E+01	77.2	8.21E-01	8.41E-01	5.
329	8.253	3.337E+00	1.721E+01	1.558E+01	75.3	9.17E-01	9.05E-01	3.
335	8.336	3.184E+00	1.330E+01	1.195E+01	79.7	8.80E-01	8.99E-01	4.
332	8.553	5.418E+00	2.080E+01	1.652E+01	80.4	9.05E-01	7.94E-01	2.
338	8.881	3.409E+00	1.067E+01	1.004E+01	79.6	7.86E-01	9.41E-01	1.

Table 30 - 20 Kt Drag (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

DRAG

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (NEWTON)	ROOTQ0 (NEWTON)	AMPLITUDE (NEWTON)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	1.184E+02	1.759E+02	2.685E+01	284.3	4.35E+00	1.53E-01	13.
301	1.506	9.960E+01	1.549E+02	2.198E+01	249.4	3.75E+00	1.42E-01	15.
342	1.530	1.069E+02	1.706E+02	7.495E+01	188.7	6.56E+01	4.39E-01	11.
348	1.757	1.121E+02	3.695E+02	3.520E+02	276.9	5.15E+01	9.52E-01	10.
351	2.243	1.233E+02	2.749E+02	2.423E+02	56.7	2.69E+01	8.81E-01	8.
303	2.273	1.040E+02	1.639E+02	1.260E+02	56.8	1.48E+01	7.69E-01	18.
306	2.938	1.139E+02	1.344E+02	1.126E+02	76.7	1.04E+01	8.38E-01	12.
309	3.790	1.255E+02	2.021E+02	1.102E+02	101.6	7.37E+00	5.44E-01	4.
312	4.360	1.206E+02	1.481E+02	8.856E+01	99.7	6.05E+00	5.98E-01	12.
315	5.073	1.114E+02	1.287E+02	6.788E+01	111.7	5.14E+00	5.27E-01	5.
318	5.790	1.090E+02	1.222E+02	4.884E+01	131.7	3.36E+00	3.99E-01	12.
354	6.233	1.073E+02	1.499E+02	2.257E+01	145.7	3.53E+00	1.50E-01	4.
366	6.260	1.634E+02	2.242E+02	1.357E+02	129.1	3.02E+00	6.05E-01	3.
360	6.290	1.145E+02	1.989E+02	7.055E+01	143.2	3.22E+00	3.55E-01	3.
357	6.361	1.064E+02	1.524E+02	3.655E+01	140.1	2.96E+00	2.40E-01	5.
363	6.372	1.289E+02	1.934E+02	8.985E+01	122.9	2.45E+00	4.65E-01	3.
321	6.397	1.097E+02	1.408E+02	5.187E+01	137.7	2.88E+00	3.68E-01	8.
324	6.786	1.100E+02	1.193E+02	4.442E+01	137.1	2.29E+00	3.72E-01	4.
370	6.899	1.736E+02	1.669E+02	5.800E+01	153.9	3.03E+00	3.47E-01	8.
330	6.922	1.105E+02	1.293E+02	3.511E+01	140.6	1.74E+00	2.72E-01	4.
333	7.242	1.069E+02	1.823E+02	3.978E+01	143.4	2.11E+00	2.18E-01	3.
336	7.393	1.056E+02	1.528E+02	3.085E+01	143.4	1.73E+00	2.02E-01	7.
339	7.468	1.012E+02	1.692E+02	3.106E+01	151.7	1.69E+00	1.84E-01	7.

Table 31 - 26 Kt Drag (Metric Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

DRAG

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (NEWTON)	ROOTQ0 (NEWTON)	AMPLITUDE (NEWTON)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	1.870E+02	1.395E+02	5.738E+01	210.5	8.63E+00	4.12E-01	2.
346	1.495	1.537E+02	1.007E+02	7.113E+01	229.7	1.11E+01	7.07E-01	9.
349	1.741	1.751E+02	1.465E+02	1.216E+02	249.9	1.77E+01	8.30E-01	8.
304	2.222	3.044E+01	3.299E+02	3.174E+02	339.9	3.58E+01	9.62E-01	16.
352	2.263	7.050E+01	5.961E+02	5.494E+02	358.5	6.16E+01	9.22E-01	26.
307	2.930	1.162E+02	1.971E+02	1.874E+02	63.2	1.76E+01	9.51E-01	10.
310	3.813	1.762E+02	2.206E+02	1.743E+02	87.7	1.15E+01	7.90E-01	10.
313	4.341	1.643E+02	2.226E+02	1.262E+02	102.4	8.23E+00	5.67E-01	12.
316	5.001	1.479E+02	1.083E+02	7.509E+01	107.3	5.42E+00	6.94E-01	10.
319	5.930	1.409E+02	8.327E+01	5.333E+01	117.4	3.88E+00	6.41E-01	7.
355	6.272	1.462E+02	6.228E+01	3.616E+01	126.1	4.64E+00	5.80E-01	3.
358	6.326	1.504E+02	8.932E+01	5.325E+01	122.3	4.17E+00	5.96E-01	9.
361	6.387	1.590E+02	1.876E+02	9.541E+01	129.2	3.97E+00	5.09E-01	5.
322	6.393	1.514E+02	1.555E+02	6.579E+01	124.0	3.85E+00	4.23E-01	9.
364	6.433	1.923E+02	2.586E+02	1.515E+02	123.3	4.11E+00	5.86E-01	8.
328	6.757	1.436E+02	1.169E+02	6.014E+01	125.1	2.91E+00	5.14E-01	17.
331	6.905	1.537E+02	1.548E+02	5.889E+01	120.0	2.81E+00	3.81E-01	5.
334	7.175	1.407E+02	1.068E+02	5.796E+01	127.1	2.97E+00	5.43E-01	5.
337	7.242	1.443E+02	1.057E+02	4.777E+01	128.4	2.43E+00	4.52E-01	5.
340	7.451	1.386E+02	8.781E+01	4.817E+01	130.7	2.63E+00	5.49E-01	10.

Table 32 - 0 Kt Wave Amplitude (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

WAVE AMPLITUDE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (IN)	ROOTQ0 (IN)	AMPLITUDE (IN)	AMPLITUDE /ROOTQ0	ENCOUNTER PERIOD (SEC)	WAVE PERIOD (SEC)	NUMBER CYCLES
300	1.491	1.084E-01	8.049E-01	7.873E-01	9.78E-01	1.455	1.455	11.
344	1.499	-1.466E-01	8.569E-01	8.450E-01	9.86E-01	1.444	1.444	4.
347	1.750	-1.525E-01	7.329E-01	7.164E-01	9.77E-01	1.560	1.560	2.
302	2.290	-3.218E-02	1.486E+00	1.476E+00	9.93E-01	1.784	1.784	5.
350	2.360	-8.352E-02	1.138E+00	1.099E+00	9.65E-01	1.812	1.812	5.
305	2.969	-1.644E-01	1.466E+00	1.453E+00	9.91E-01	2.037	2.037	6.
308	3.933	-5.245E-02	1.974E+00	1.959E+00	9.92E-01	2.365	2.365	6.
311	4.564	-1.106E-01	2.141E+00	2.127E+00	9.94E-01	2.571	2.571	5.
314	5.332	-1.046E-01	1.783E+00	1.756E+00	9.85E-01	2.826	2.826	4.
317	6.488	-1.177E-01	2.296E+00	2.275E+00	9.91E-01	3.203	3.203	6.
320	7.206	-1.364E-01	2.834E+00	2.792E+00	9.85E-01	3.458	3.458	4.
356	7.248	-9.273E-02	1.998E+00	1.981E+00	9.80E-01	3.473	3.473	5.
359	7.272	-1.267E-01	2.681E+00	2.596E+00	9.68E-01	3.481	3.481	5.
362	7.291	-2.552E-01	3.649E+00	3.551E+00	9.73E-01	3.488	3.488	5.
353	7.333	-3.865E-02	1.004E+00	9.736E-01	9.70E-01	3.492	3.492	5.
365	7.433	-3.808E-01	5.181E+00	4.985E+00	9.62E-01	3.525	3.525	5.
326	8.057	-7.216E-02	2.893E+00	2.839E+00	9.81E-01	3.750	3.750	1.
368	8.078	1.086E-01	2.465E+00	2.414E+00	9.79E-01	3.758	3.758	5.
329	8.253	-8.964E-02	2.306E+00	2.251E+00	9.76E-01	3.820	3.820	3.
335	8.336	-5.788E-02	1.911E+00	1.799E+00	9.42E-01	3.850	3.850	4.
332	8.553	-8.359E-02	2.489E+00	2.418E+00	9.72E-01	3.929	3.929	2.
338	8.881	-1.335E-01	1.731E+00	1.692E+00	9.77E-01	4.026	4.026	1.

Table 33 - 20 Kt Wave Amplitude (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

WAVE AMPLITUDE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (IN)	ROOTQ0 (IN)	AMPLITUDE (IN)	AMPLITUDE /ROOTQ0	ENCOUNTER PERIOD (SEC)	WAVE PERIOD (SEC)	NUMBER CYCLES
345	1.489	-2.069E-01	8.461E-01	8.187E-01	9.68E-01	.256	1.439	13.
301	1.506	-1.194E-01	7.808E-01	7.764E-01	9.94E-01	.259	1.447	15.
342	1.530	4.892E-03	1.863E-01	1.514E-01	8.13E-01	.262	1.458	11.
348	1.757	-1.945E-01	9.600E-01	9.062E-01	9.44E-01	.298	1.563	10.
351	2.243	-1.314E-01	1.275E+00	1.193E+00	9.35E-01	.370	1.766	8.
303	2.273	-5.882E-02	1.204E+00	1.127E+00	9.36E-01	.375	1.778	18.
306	2.938	-1.771E-01	1.497E+00	1.439E+00	9.61E-01	.474	2.026	12.
309	3.790	-1.342E-01	2.012E+00	1.980E+00	9.84E-01	.599	2.317	4.
312	4.360	-1.306E-01	1.961E+00	1.940E+00	9.89E-01	.686	2.506	12.
315	5.073	-1.863E-01	1.823E+00	1.748E+00	9.59E-01	.800	2.740	5.
318	5.790	-1.200E-01	1.977E+00	1.923E+00	9.73E-01	.921	2.976	12.
354	6.233	-1.861E-01	9.027E-01	8.460E-01	9.37E-01	.997	3.120	4.
366	6.260	-3.965E-01	6.201E+00	5.945E+00	9.59E-01	1.001	3.128	3.
360	6.290	-2.617E-01	3.008E+00	2.900E+00	9.64E-01	1.007	3.138	3.
357	6.361	-2.094E-01	1.675E+00	1.637E+00	9.77E-01	1.019	3.162	5.
363	6.372	-3.080E-01	5.005E+00	4.867E+00	9.72E-01	1.022	3.165	3.
321	6.397	-1.815E-01	2.467E+00	2.381E+00	9.65E-01	1.026	3.730	8.
327	6.786	4.059E-02	2.648E+00	2.564E+00	9.68E-01	1.100	3.312	4.
370	6.899	-3.304E-01	2.577E+00	2.536E+00	9.84E-01	1.122	3.351	8.
330	6.922	-1.518E-01	2.750E+00	2.678E+00	9.74E-01	1.127	3.359	4.
333	7.242	-1.189E-01	2.601E+00	2.492E+00	9.58E-01	1.190	3.471	3.
336	7.393	-1.170E-01	2.456E+00	2.359E+00	9.60E-01	1.213	3.512	7.
339	7.468	-1.274E-01	2.549E+00	2.441E+00	9.58E-01	1.228	3.537	7.

Table 34 - 26 Kt Wave Amplitude (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

WAVE AMPLITUDE

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (IN)	ROOTQ0 (IN)	AMPLITUDE (IN)	AMPLITUDE /ROOTQ0	ENCOUNTER PERIOD (SEC)	WAVE PERIOD (SEC)	NUMBER CYCLES
343	1.213	-2.263E-01	8.922E-01	8.807E-01	9.87E-01	.170	1.299	2.
346	1.495	-9.019E-02	8.627E-01	8.463E-01	9.81E-01	.206	1.442	9.
349	1.741	-5.010E-02	9.285E-01	9.127E-01	9.83E-01	.237	1.556	8.
304	2.222	-3.565E-02	1.193E+00	1.174E+00	9.84E-01	.297	1.758	16.
352	2.263	-5.722E-02	1.280E+00	1.181E+00	9.23E-01	.302	1.771	26.
307	2.930	-1.521E-01	1.446E+00	1.412E+00	9.77E-01	.384	2.023	10.
310	3.813	-6.511E-02	2.016E+00	2.008E+00	9.96E-01	.493	2.325	10.
313	4.341	-1.580E-01	2.069E+00	2.003E+00	9.83E-01	.560	2.498	12.
316	5.001	-2.154E-01	1.921E+00	1.834E+00	9.55E-01	.647	2.711	10.
319	5.930	-2.460E-01	1.979E+00	1.822E+00	9.21E-01	.782	3.020	7.
355	6.272	-5.719E-02	1.076E+00	1.033E+00	9.60E-01	.832	3.132	3.
358	6.326	-2.249E-01	1.735E+00	1.690E+00	9.74E-01	.841	3.150	9.
361	6.387	-2.405E-01	3.248E+00	3.187E+00	9.81E-01	.850	3.170	5.
322	6.393	-2.086E-01	2.598E+00	2.266E+00	8.72E-01	.860	3.190	9.
364	6.433	-1.184E-01	5.028E+00	4.887E+00	9.72E-01	.857	3.185	8.
328	6.757	-3.535E-03	2.777E+00	2.737E+00	9.86E-01	.912	3.302	17.
331	6.905	-9.692E-02	2.847E+00	2.779E+00	9.76E-01	.936	3.353	5.
334	7.175	-7.362E-02	2.689E+00	2.589E+00	9.63E-01	.982	3.447	5.
337	7.242	-6.475E-02	2.662E+00	2.603E+00	9.78E-01	.994	3.471	5.
340	7.451	-1.066E-01	2.522E+00	2.430E+00	9.64E-01	1.024	3.532	10.

Table 35 - 0 Kt Heave (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

HEAVE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (IN)	ROOTQ0 (IN)	AMPLITUDE (IN)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	3.374E-01	3.518E-01	3.321E-01	181.2	4.22E-01	9.44E-01	11.
344	1.499	7.192E-01	4.102E-01	4.020E-01	181.2	4.76E-01	9.80E-01	4.
347	1.750	1.088E+00	6.877E-01	6.863E-01	187.9	9.58E-01	9.98E-01	2.
302	2.291	4.542E-01	8.475E-01	8.361E-01	175.1	5.66E-01	9.87E-01	5.
350	2.360	2.530E+00	8.647E-01	8.299E-01	169.4	7.55E-01	9.60E-01	5.
305	2.969	2.141E-01	1.097E+00	1.091E+00	176.4	7.51E-01	9.94E-01	6.
308	3.933	6.297E-01	1.848E+00	1.843E+00	181.8	9.41E-01	9.97E-01	6.
311	4.564	4.757E-01	1.952E+00	1.942E+00	175.0	9.13E-01	9.95E-01	5.
314	5.332	8.722E-01	1.871E+00	1.852E+00	168.7	1.05E+00	9.90E-01	4.
317	6.488	1.137E+00	1.982E+00	1.967E+00	157.8	8.65E-01	9.93E-01	6.
320	7.206	8.965E-01	2.046E+00	2.018E+00	164.8	7.23E-01	9.87E-01	4.
356	7.248	6.407E-01	1.470E+00	1.456E+00	159.8	7.35E-01	9.90E-01	5.
359	7.272	4.421E-01	3.437E+00	3.340E+00	165.9	1.29E+00	9.72E-01	5.
362	7.291	3.570E-01	4.798E+00	4.681E+00	-175.4	1.32E+00	9.75E-01	5.
353	7.333	6.155E-01	6.646E-01	6.543E-01	109.3	6.72E-01	9.85E-01	5.
365	7.433	7.279E-01	6.604E+00	6.428E+00	172.2	1.29E+00	9.73E-01	5.
326	8.057	4.437E-01	2.404E+00	2.359E+00	163.2	8.31E-01	9.81E-01	1.
368	8.078	5.592E-01	2.719E+00	2.674E+00	160.0	1.11E+00	9.83E-01	5.
329	8.253	3.353E-01	3.025E+00	2.963E+00	-178.1	1.32E+00	9.79E-01	3.
335	8.336	4.682E-01	2.872E+00	2.703E+00	189.9	1.50E+00	9.41E-01	4.
332	8.553	5.267E-01	2.265E+00	2.206E+00	198.7	9.13E-01	9.74E-01	2.
338	8.881	6.235E-01	2.966E+00	2.947E+00	179.8	1.74E+00	9.94E-01	1.

Table 36 - 20 Kt Heave (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

HEAVE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (IN)	ROOTQ0 (IN)	AMPLITUDE (IN)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	3.295E-01	1.986E-01	1.383E-01	62.5	1.69E-01	6.96E-01	13.
301	1.506	7.976E-01	1.541E-01	1.318E-01	47.6	1.70E-01	8.55E-01	15.
342	1.530	9.775E-03	7.305E-02	2.173E-02	65.5	1.44E-01	2.97E-01	11.
348	1.757	5.076E-01	3.712E-01	2.930E-01	79.8	3.23E-01	7.90E-01	10.
351	2.243	5.719E-01	8.196E-01	6.699E-01	93.8	5.62E-01	8.17E-01	8.
303	2.273	4.832E-01	8.912E-01	6.843E-01	89.2	6.07E-01	7.68E-01	18.
306	2.938	6.402E-01	1.504E+00	1.400E+00	112.1	9.73E-01	9.31E-01	12.
309	3.790	5.399E-01	2.437E+00	2.410E+00	137.2	1.22E+00	9.89E-01	4.
312	4.360	5.443E-01	2.635E+00	2.611E+00	146.4	1.35E+00	9.91E-01	12.
315	5.073	6.499E-01	2.465E+00	2.376E+00	156.7	1.36E+00	9.64E-01	5.
318	5.790	3.884E-01	2.489E+00	2.445E+00	174.8	1.27E+00	9.82E-01	12.
354	6.233	3.907E-01	1.133E+00	1.083E+00	180.4	1.28E+00	9.56E-01	4.
366	6.260	3.275E-01	8.222E+00	8.031E+00	176.7	1.35E+00	9.77E-01	3.
360	6.290	4.639E-01	3.735E+00	3.624E+00	187.6	1.25E+00	9.70E-01	3.
357	6.361	2.498E-01	2.142E+00	2.099E+00	182.0	1.28E+00	9.80E-01	5.
363	6.372	3.067E-01	5.711E+00	5.585E+00	174.4	1.15E+00	9.78E-01	3.
321	6.397	4.903E-01	3.052E+00	2.971E+00	179.2	1.25E+00	9.74E-01	8.
327	6.786	-1.519E-01	3.152E+00	3.116E+00	183.0	1.22E+00	9.89E-01	4.
370	6.899	3.334E+00	3.033E+00	3.000E+00	-173.1	1.18E+00	9.89E-01	8.
330	6.922	8.186E-02	3.247E+00	3.175E+00	188.0	1.19E+00	9.78E-01	4.
333	7.242	-5.776E-02	3.009E+00	2.922E+00	188.0	1.17E+00	9.71E-01	3.
336	7.393	-8.321E-02	2.891E+00	2.792E+00	185.6	1.18E+00	9.66E-01	7.
339	7.468	-5.092E-02	2.833E+00	2.728E+00	-170.5	1.12E+00	9.63E-01	7.

Table 37 - 26 Kt Heave (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

HEAVE

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (IN)	ROOTQ0 (IN)	AMPLITUDE (IN)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	5.207E-01	7.054E-02	1.480E-02	84.7	1.68E-02	2.10E-01	2.
346	1.495	2.704E-01	1.070E-01	8.307E-02	27.5	9.82E-02	7.76E-01	9.
349	1.741	1.054E+00	2.118E-01	1.380E-01	51.5	1.51E-01	6.51E-01	8.
304	2.222	8.865E-01	5.473E-01	4.993E-01	76.1	4.25E-01	9.12E-01	16.
352	2.263	8.043E-01	5.716E-01	4.684E-01	85.2	3.97E-01	8.19E-01	26.
307	2.930	1.038E+00	1.295E+00	1.205E+00	90.3	8.54E-01	9.31E-01	10.
310	3.813	7.700E-01	2.240E+00	2.218E+00	119.9	1.10E+00	9.90E-01	10.
313	4.341	6.883E-01	2.441E+00	2.396E+00	136.3	1.18E+00	9.81E-01	12.
316	5.001	4.746E-01	2.294E+00	2.192E+00	150.2	1.20E+00	9.56E-01	10.
319	5.930	3.973E-01	2.293E+00	2.060E+00	164.8	1.13E+00	8.99E-01	7.
355	6.272	9.280E+02	1.225E+00	1.182E+00	172.2	1.14E+00	9.65E-01	3.
358	6.326	2.586E-01	1.993E+00	1.935E+00	173.8	1.15E+00	9.71E-01	9.
361	6.387	4.532E-01	3.676E+00	3.613E+00	175.4	1.13E+00	9.83E-01	5.
322	6.393	7.840E-01	2.937E+00	2.604E+00	170.3	1.15E+00	8.87E-01	9.
364	6.433	1.161E+00	5.967E+00	5.786E+00	169.9	1.18E+00	9.70E-01	8.
328	6.757	-2.990E-01	3.215E+00	3.179E+00	176.7	1.16E+00	9.89E-01	17.
331	6.905	-4.956E-02	3.389E+00	3.237E+00	176.3	1.16E+00	9.55E-01	5.
334	7.175	-9.426E-02	2.157E+00	2.973E+00	-180.7	1.15E+00	9.75E-01	5.
337	7.242	-1.080E-01	3.046E+00	2.989E+00	179.3	1.15E+00	9.81E-01	5.
340	7.451	-1.230E-01	2.969E+00	2.846E+00	181.5	1.17E+00	9.59E-01	10.

Table 38 - 0 Kt Relative Bow Motion (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

RELATIVE BOW MOTION

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (IN)	ROOTQO (IN)	AMPLITUDE (IN)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQO	NUMBER OF CYCLES
300	1.491	-1.209E-01	1.925E+00	1.533E-01	186.8	9.57E-01	3.91E-01	11.
344	1.499	-3.794E-01	4.130E+00	2.186E+00	220.4	2.59E+00	5.29E-01	4.
347	1.750	6.790E-01	3.245E+00	2.311E+00	201.6	3.23E+00	7.12E-01	2.
302	2.290	9.531E-01	2.191E+00	1.020E+00	170.8	6.91E-01	4.66E-01	5.
350	2.360	5.017E-01	2.559E+00	1.667E+00	193.7	1.52E+00	6.51E-01	5.
305	2.969	4.445E-01	1.597E+00	9.303E-01	170.5	6.40E-01	5.83E-01	6.
308	3.933	-4.969E+00	8.974E+00	2.826E+00	110.0	1.44E+00	3.15E-01	6.
311	4.564	-3.052E+00	8.037E+00	3.107E+00	135.0	1.46E+00	3.87E-01	5.
314	5.332	-3.657E+00	8.833E+00	2.078E+00	167.6	1.18E+00	2.35E-01	4.
317	6.488	-3.708E+00	8.924E+00	2.339E+00	158.7	1.03E+00	2.62E-01	6.
320	7.206	-6.167E-01	5.691E+00	4.289E-01	232.8	1.54E-01	7.54E-02	4.
356	7.248	-4.525E-02	2.919E+00	5.246E-01	167.3	2.65E-01	1.80E-01	5.
359	7.272	2.144E-01	1.807E+00	6.659E-01	185.9	2.57E-01	3.68E-01	5.
362	7.291	2.928E-01	1.579E+00	1.006E+00	-174.4	2.83E-01	6.37E-01	5.
353	7.333	-1.582E-01	3.744E+00	1.062E-01	-116.0	1.09E-01	2.84E-02	5.
365	7.433	-1.091E-01	2.241E+00	1.414E+00	168.2	2.84E-01	6.31E-01	5.
326	8.057	-8.083E-02	2.916E+00	4.611E-01	276.3	1.62E-01	1.58E-01	1.
368	8.078	-4.027E-02	2.781E+00	5.369E-01	141.7	2.22E-01	1.93E-01	5.
329	8.253	1.719E-01	1.543E+00	5.600E-01	-165.7	2.49E-01	3.63E-01	3.
335	8.336	1.836E-01	1.781E+00	2.677E-01	219.2	1.49E-01	1.50E-01	4.
332	8.553	-4.778E-01	3.471E+00	8.773E-01	184.5	3.63E-01	2.53E-01	2.
338	8.881	5.817E-02	2.017E+00	3.118E-01	234.8	1.84E-01	1.55E-01	1.

Table 39 - 20 Kt Relative Bow Motion (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

RELATIVE BOW MOTION

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (IN)	ROOTQ0 (IN)	AMPLITUDE (IN)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	-3.516E-01	1.045E+00	9.807E-01	150.6	1.20E+00	9.39E-01	13.
342	1.530	-5.897E-01	3.337E-01	2.437E-01	136.6	1.61E+00	7.30E-01	11.
301	1.560	5.038E-01	1.081E+00	9.515E-01	128.3	1.23E+00	8.80E-01	15.
348	1.757	2.631E-01	1.572E+00	1.332E+00	129.9	1.47E+00	8.47E-01	10.
351	2.243	5.056E-01	2.190E+00	1.974E+00	115.0	1.66E+00	9.01E-01	8.
303	2.273	6.606E-01	2.387E+00	1.365E+00	116.2	1.21E+00	5.72E-01	18.
306	2.938	1.054E+00	2.904E+00	1.915E+00	112.9	1.33E+00	6.60E-01	12.
309	3.790	-1.219E+00	6.009E+00	4.490E+00	115.1	2.27E+00	7.47E-01	4.
312	4.360	-9.001E-01	6.546E+00	5.002E+00	129.2	2.58E+00	7.64E-01	12.
315	5.073	-3.094E+00	8.548E+00	5.951E+00	140.7	3.40E+00	6.96E-01	5.
318	5.790	-1.909E+00	6.432E+00	3.753E+00	160.3	1.95E+00	5.84E-01	12.
354	6.233	-1.966E-01	8.459E-01	7.441E-01	175.1	8.80E-01	8.80E-01	4.
366	6.260	2.086E-01	7.310E+00	6.744E+00	131.2	1.13E+00	9.23E-01	3.
360	6.290	-1.693E-01	2.482E+00	2.346E+00	171.2	8.09E-01	9.45E-01	3.
357	6.361	-3.357E-01	1.501E+00	1.451E+00	172.2	8.86E-01	9.67E-01	5.
363	6.372	-9.777E-02	4.418E+00	4.109E+00	136.7	8.44E-01	9.30E-01	3.
321	6.397	-1.660E+00	6.022E+00	3.837E+00	146.9	1.61E+00	6.37E-01	8.
327	6.786	-1.283E+00	1.790E+00	1.726E+00	166.6	6.73E-01	9.64E-01	4.
370	6.899	5.823E+00	1.376E+00	1.199E+00	-172.8	4.73E-01	8.71E-01	8.
330	6.922	-1.128E+00	1.792E+00	1.672E+00	175.3	6.24E-01	9.33E-01	4.
333	7.242	-1.142E+00	1.529E+00	1.442E+00	180.7	5.78E-01	9.43E-01	3.
336	7.393	-1.259E+00	1.305E+00	1.221E+00	181.1	5.18E-01	9.35E-01	7.
339	7.468	-1.260E+00	1.192E+00	1.106E+00	-170.6	4.53E-01	9.27E-01	7.

Table 40 - 26 Kt Relative Bow Motion (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

RELATIVE BOW MOTION

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (IN)	ROOTQ0 (IN)	AMPLITUDE (IN)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	8.313E-01	1.064E+00	1.030E+00	195.1	1.17E+00	9.68E-01	2.
346	1.495	3.131E-01	9.786E-01	9.622E-01	150.2	1.14E+00	9.83E-01	9.
349	1.741	2.753E+00	1.195E+00	1.137E+00	128.7	1.25E+00	9.51E-01	8.
304	2.222	1.506E+00	1.774E+00	1.720E+00	107.7	1.47E+00	9.70E-01	16.
352	2.263	1.907E+00	1.885E+00	1.725E+00	113.3	1.46E+00	9.15E-01	26.
307	2.930	2.024E+00	2.383E+00	2.277E+00	91.6	1.61E+00	9.56E-01	10.
310	3.813	1.862E+00	3.264E+00	3.174E+00	95.3	1.58E+00	9.73E-01	10.
313	4.341	1.127E+00	3.814E+00	3.180E+00	100.1	1.56E+00	8.34E-01	12.
316	5.001	-1.321E+00	7.033E+00	3.975E+00	103.8	2.17E+00	5.65E-01	10.
319	5.930	-2.753E+00	7.869E+00	3.681E+00	102.5	2.02E+00	4.68E-01	7.
355	6.272	6.435E-01	9.127E-01	8.447E-01	124.4	8.18E-01	9.25E-01	3.
358	6.326	5.322E-01	1.592E+00	1.452E+00	125.2	8.60E-01	9.13E-01	9.
361	6.387	1.078E+00	2.567E+00	2.515E+00	126.1	7.89E-01	9.80E-01	5.
322	6.393	3.492E-01	4.120E+00	2.469E+00	103.8	1.09E+00	5.99E-01	9.
364	6.433	2.533E+00	4.653E+00	4.390E+00	116.2	8.98E-01	9.44E-01	8.
328	6.757	-6.465E-01	2.373E+00	2.315E+00	127.3	8.46E-01	9.75E-01	17.
331	6.905	-3.856E-01	2.743E+00	2.548E+00	124.3	9.17E-01	9.29E-01	5.
334	7.175	-5.633E-01	1.911E+00	1.849E+00	-224.5	7.14E-01	9.67E-01	5.
337	7.242	-8.711E-01	2.094E+00	2.026E+00	136.6	7.78E-01	9.68E-01	5.
340	7.451	-6.030E-01	1.837E+00	1.724E+00	140.9	7.09E-01	9.38E-01	10.

Table 41 - 0 Kt Average Cushion Pressure (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AVERAGE CUSHION PRESSURE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PSI)	ROOTQ0 (PSI)	AMPLITUDE (PSI)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	5.750E-02	4.115E-03	7.281E-04	186.4	3.98E+00	1.77E-01	11.
344	1.499	5.705E-02	4.299E-03	4.172E-04	148.9	2.12E+00	9.70E-02	4.
347	1.750	5.807E-02	5.120E-03	4.960E-04	169.9	2.98E+00	9.69E-02	2.
302	2.290	5.751E-02	4.408E-03	8.699E-04	171.1	2.53E+00	1.97E-01	5.
350	2.360	6.003E-02	4.540E-03	1.213E-03	153.7	4.75E+00	2.67E-01	5.
305	2.969	5.943E-02	4.148E-03	1.467E-03	165.1	4.34E+00	3.54E-01	6.
308	3.933	5.977E-02	4.718E-03	1.008E-03	157.5	2.21E+00	2.14E-01	6.
311	4.564	6.009E-02	4.700E-03	1.693E-03	156.9	3.42E+00	3.60E-01	5.
314	5.332	5.950E-02	5.373E-03	1.031E-03	135.6	2.53E+00	1.92E-01	4.
317	6.488	5.690E-02	5.867E-03	1.051E-03	137.5	1.99E+00	1.79E-01	6.
320	7.206	6.088E-02	5.400E-03	1.107E-03	142.6	1.71E+00	2.05E-01	4.
356	7.248	5.662E-02	5.660E-03	6.731E-04	116.4	1.46E+00	1.19E-01	5.
359	7.272	6.122E-02	5.062E-03	1.467E-03	151.5	2.43E+00	2.90E-01	5.
362	7.291	6.378E-02	4.931E-03	2.064E-03	-182.7	2.50E+00	4.19E-01	5.
353	7.333	5.863E-02	4.733E-03	3.625E-04	136.5	1.60E+00	7.66E-02	5.
365	7.433	5.998E-02	5.695E-03	2.896E-03	165.1	2.50E+00	5.08E-01	5.
326	8.057	5.768E-02	5.137E-03	8.145E-04	148.9	1.23E+00	1.59E-01	1.
368	8.078	5.826E-02	4.935E-03	1.074E-03	136.3	1.91E+00	2.18E-01	5.
329	8.253	5.548E-02	5.109E-03	1.137E-03	-199.1	2.17E+00	2.23E-01	3.
335	8.336	5.947E-02	4.496E-03	1.007E-03	165.0	2.41E+00	2.24E-01	4.
332	8.553	5.882E-02	4.832E-03	9.411E-04	180.3	1.67E+00	1.95E-01	2.
338	8.881	5.685E-02	4.762E-03	8.302E-04	172.4	2.11E+00	1.74E-01	1.

Table 42 - 20 Kt Average Cushion Pressure (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AVERAGE CUSHION PRESSURE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PSI)	ROOTQ0 (PSI)	AMPLITUDE (PSI)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	4.568E-02	1.752E-02	1.658E-02	63.4	8.71E+01	9.47E-01	13.
301	1.506	4.630E-02	1.552E-02	1.494E-02	54.6	8.28E+01	9.62E-01	15.
342	1.530	4.257E-02	6.634E-03	4.387E-03	89.8	1.25E+02	6.61E-01	11.
348	1.757	5.152E-02	2.613E-02	2.430E-02	76.7	1.15E+02	9.30E-01	10.
351	2.243	4.956E-02	3.274E-02	3.112E-02	91.1	1.12E+02	9.50E-01	8.
303	2.273	4.658E-02	3.172E-02	3.056E-02	86.4	1.17E+02	9.63E-01	18.
306	2.938	4.782E-02	3.930E-02	3.787E-02	108.0	1.13E+02	9.64E-01	12.
309	3.790	4.729E-02	4.113E-02	3.883E-02	129.9	8.44E+01	9.44E-01	4.
312	4.360	4.995E-02	3.525E-02	3.375E-02	139.7	7.48E+01	9.58E-01	12.
315	5.073	4.856E-02	2.442E-02	2.322E-02	151.0	5.71E+01	9.51E-01	5.
318	5.790	4.693E-02	1.774E-02	1.694E-02	168.8	3.79E+01	9.55E-01	12.
354	6.233	4.947E-02	8.688E-03	5.971E-03	174.7	3.04E+01	6.87E-01	4.
366	6.260	4.653E-02	5.772E-02	4.380E-02	166.2	3.17E+01	7.59E-01	3.
360	6.290	5.132E-02	2.117E-02	1.905E-02	180.9	2.83E+01	9.00E-01	3.
357	6.361	4.782E-02	1.301E-02	1.196E-02	175.7	3.14E+01	9.20E-01	5.
363	6.372	4.925E-02	3.421E-02	3.046E-02	164.2	2.69E+01	8.90E-01	3.
321	6.397	4.906E-02	1.804E-02	1.679E-02	172.3	3.03E+01	9.31E-01	8.
327	6.786	4.631E-02	1.602E-02	1.522E-02	177.1	2.55E+01	9.50E-01	4.
370	6.899	5.177E-02	1.410E-02	1.145E-02	-178.7	1.94E+01	8.12E-01	8.
330	6.922	4.284E-02	1.693E-02	1.479E-02	180.9	2.37E+01	8.73E-01	4.
333	7.242	4.839E-02	1.406E-02	1.215E-02	181.9	2.10E+01	8.64E-01	3.
336	7.393	4.724E-02	1.260E-02	1.127E-02	179.6	2.05E+01	8.94E-01	7.
339	7.468	4.493E-02	1.157E-02	1.023E-02	-176.0	1.80E+01	8.84E-01	7.

Table 43 - 26 Kt Average Cushion Pressure (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AVERAGE CUSHION PRESSURE

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PSI)	ROOTQO (PSI)	AMPLITUDE (PSI)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQO	NUMBER OF CYCLES
343	1.213	3.704E-02	1.324E-02	1.142E-02	301.4	5.58E+01	8.62E-01	2.
346	1.495	4.102E-02	1.792E-02	1.654E-02	39.3	8.41E+01	9.23E-01	9.
349	1.741	4.745E-02	2.178E-02	1.974E-02	47.3	9.30E+01	9.06E-01	8.
304	2.222	4.439E-02	3.802E-02	3.612E-02	67.1	1.32E+02	9.50E-01	16.
352	2.263	4.706E-02	3.688E-02	3.334E-02	75.4	1.21E+02	9.04E-01	26.
307	2.930	4.601E-02	5.409E-02	4.912E-02	81.8	1.50E+02	9.08E-01	10.
310	3.813	4.557E-02	5.698E-02	5.042E-02	110.2	1.08E+02	8.85E-01	10.
313	4.341	4.664E-02	4.783E-02	4.412E-02	126.6	9.34E+01	9.22E-01	12.
316	5.001	4.355E-02	3.262E-02	3.061E-02	140.0	7.18E+01	9.38E-01	10.
319	5.930	4.263E-02	2.407E-02	2.123E-02	151.7	5.01E+01	8.82E-01	7.
355	6.272	4.426E-02	1.194E-02	1.058E-02	158.8	4.41E+01	8.86E-01	3.
358	6.326	4.316E-02	1.721E-02	1.630E-02	160.8	4.15E+01	9.47E-01	9.
361	6.387	4.780E-02	3.108E-02	2.881E-02	164.4	3.89E+01	9.27E-01	5.
322	6.393	4.660E-02	2.491E-02	2.149E-02	158.2	4.08E+01	8.63E-01	9.
364	6.433	5.062E-02	5.061E-02	4.316E-02	155.3	3.80E+01	8.53E-01	8.
328	6.757	4.185E-02	2.486E-02	2.307E-02	163.7	3.63E+01	9.28E-01	17.
331	6.905	3.892E-02	2.535E-02	2.254E-02	160.9	3.49E+01	8.89E-01	5.
334	7.175	4.253E-02	2.026E-02	1.897E-02	-194.9	3.15E+01	9.36E-01	5.
337	7.242	4.222E-02	2.017E-02	1.842E-02	165.6	3.04E+01	9.13E-01	5.
340	7.451	3.997E-02	1.882E-02	1.703E-02	168.2	3.01E+01	9.05E-01	10.

Table 44 - 0 Kt Forward Cushion Pressure (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

FORWARD CUSHION PRESSURE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PSI)	ROOTQ0 (PSI)	AMPLITUDE (PSI)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	6.629E-02	4.947E-03	3.201E-03	185.2	1.75E+01	6.47E-01	11.
344	1.499	7.020E-02	4.598E-03	2.357E-03	214.0	1.20E+01	5.12E-01	4.
347	1.750	6.732E-02	5.688E-03	2.696E-03	204.6	1.62E+01	4.74E-01	2.
302	2.290	7.019E-02	5.079E-03	2.861E-03	182.2	8.34E+00	5.63E-01	5.
350	2.360	6.780E-02	4.818E-03	2.966E-03	177.6	1.16E+01	6.16E-01	5.
305	2.969	6.910E-02	5.106E-03	3.727E-03	187.8	1.01E+01	7.30E-01	6.
308	3.933	7.155E-02	4.850E-03	2.577E-03	178.4	5.66E+00	5.31E-01	6.
311	4.564	6.669E-02	5.419E-03	3.156E-03	173.5	3.42E+00	3.60E-01	5.
314	5.332	6.565E-02	5.451E-03	2.139E-03	162.9	5.24E+00	3.92E-01	4.
317	6.488	6.708E-02	5.987E-03	1.842E-03	154.7	3.48E+00	3.08E-01	6.
320	7.206	6.897E-02	5.356E-03	1.806E-03	170.8	2.78E+00	3.37E-01	4.
356	7.248	6.656E-02	5.183E-03	9.917E-04	146.5	2.15E+00	1.91E-01	5.
359	7.272	7.014E-02	5.192E-03	2.674E-03	159.7	4.43E+00	5.15E-01	5.
362	7.291	7.280E-02	5.293E-03	3.158E-03	-173.6	3.83E+00	5.97E-01	5.
353	7.333	6.693E-02	3.874E-03	7.194E-04	162.1	3.18E+00	1.86E-01	5.
365	7.433	7.381E-02	8.310E-03	5.865E-03	174.2	5.06E+00	7.06E-01	5.
326	8.057	6.901E-02	5.523E-03	1.457E-03	163.1	2.21E+00	2.64E-01	1.
368	8.078	7.168E-02	4.794E-03	1.766E-03	153.0	3.15E+00	3.68E-01	5.
329	8.253	7.207E-02	5.198E-03	1.396E-03	-203.6	2.67E+00	2.44E-01	3.
335	8.336	7.056E-02	4.330E-03	1.864E-03	174.6	4.46E+00	4.30E-01	4.
332	8.553	7.043E-02	4.215E-03	1.735E-03	191.3	3.09E+00	4.12E-01	2.
338	8.881	7.360E-02	4.717E-03	1.079E-03	171.5	2.74E+00	2.29E-01	1.

Table 45 - 20 Kt Forward Cushion Pressure (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

FORWARD CUSHION PRESSURE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PSI)	ROOTQ0 (PSI)	AMPLITUDE (PSI)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	5.676E-02	1.949E-02	1.830E-02	86.7	9.61E+01	9.39E-01	13.
301	1.506	5.669E-02	2.270E-02	2.026E-02	77.7	1.12E+02	8.92E-01	15.
342	1.530	5.861E-02	9.608E-03	6.803E-03	96.6	1.93E+02	7.08E-01	11.
348	1.757	5.915E-02	3.313E-02	3.111E-02	85.5	1.48E+02	9.39E-01	10.
351	2.243	5.760E-02	4.419E-02	4.180E-02	96.5	1.51E+02	9.46E-01	8.
303	2.273	5.368E-02	4.409E-02	4.106E-02	93.9	1.57E+02	9.31E-01	18.
306	2.938	5.641E-02	5.525E-02	5.277E-02	110.7	1.58E+02	9.55E-01	12.
309	3.790	5.300E-02	5.755E-02	5.491E-02	128.0	1.19E+02	9.54E-01	4.
312	4.360	5.728E-02	5.152E-02	5.005E-02	138.4	1.11E+02	9.72E-01	12.
315	5.073	5.689E-02	3.726E-02	3.588E-02	151.9	8.83E+01	9.63E-01	5.
318	5.790	5.554E-02	2.820E-02	2.724E-02	169.8	6.09E+01	9.66E-01	12.
354	6.233	6.029E-02	1.272E-02	9.635E-03	180.7	4.90E+01	7.58E-01	4.
366	6.260	5.474E-02	6.908E-02	5.901E-02	164.1	4.27E+01	8.54E-01	3.
360	6.290	6.072E-02	3.071E-02	2.789E-02	186.5	4.14E+01	9.08E-01	3.
357	6.361	5.879E-02	1.995E-02	1.887E-02	181.0	4.96E+01	9.46E-01	5.
363	6.372	5.396E-02	4.738E-02	4.378E-02	161.4	3.87E+01	9.24E-01	3.
321	6.397	5.652E-02	2.780E-02	2.627E-02	175.7	4.75E+01	9.45E-01	8.
327	6.786	5.818E-02	2.378E-02	2.302E-02	182.2	3.86E+01	9.68E-01	4.
370	6.899	6.816E-02	2.080E-02	1.702E-02	-172.7	2.89E+01	8.18E-01	8.
330	6.922	5.686E-02	2.487E-02	2.175E-02	186.8	3.49E+01	8.75E-01	4.
333	7.242	5.956E-02	2.087E-02	1.824E-02	187.5	3.15E+01	8.74E-01	3.
336	7.393	5.873E-02	1.899E-02	1.723E-02	185.7	3.14E+01	9.07E-01	7.
339	7.468	5.980E-02	1.637E-02	1.480E-02	-168.8	2.61E+01	9.05E-01	7.

Table 46 - 26 Kt Forward Cushion Pressure (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

FORWARD CUSHION PRESSURE

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PSI)	ROOTQ0 (PSI)	AMPLITUDE (PSI)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	5.413E-02	3.005E-02	2.968E-02	196.3	1.45E+02	9.88E-01	2.
346	1.495	5.203E-02	1.490E-02	1.364E-02	89.9	6.93E+01	9.15E-01	9.
349	1.741	5.774E-02	1.959E-02	1.840E-02	74.3	8.67E+01	9.39E-01	8.
304	2.222	5.407E-02	6.465E-02	6.597E-02	115.9	2.42E+02	9.61E-01	16.
352	2.263	4.698E-02	5.164E-02	4.447E-02	104.8	1.62E+02	8.61E-01	26.
307	2.930	4.440E-02	5.151E-02	4.542E-02	92.0	1.38E+02	8.82E-01	10.
310	3.813	5.036E-02	6.714E-02	6.010E-02	105.8	1.29E+02	8.95E-01	10.
313	4.341	5.257E-02	5.961E-02	5.519E-02	119.4	1.17E+02	9.26E-01	12.
316	5.001	5.001E-02	4.494E-02	4.205E-02	133.0	9.86E+01	9.36E-01	10.
319	5.930	5.057E-02	3.467E-02	3.093E-02	145.9	7.30E+01	8.92E-01	7.
355	6.272	5.502E-02	1.687E-02	1.549E-02	155.2	6.45E+01	9.18E-01	3.
358	6.326	5.473E-02	2.511E-02	2.406E-02	157.8	6.13E+01	9.58E-01	9.
361	6.387	5.766E-02	4.173E-02	3.958E-02	161.8	5.34E+01	9.49E-01	5.
322	6.393	5.484E-02	3.508E-02	3.060E-02	154.0	5.81E+01	8.72E-01	9.
364	6.433	5.597E-02	6.214E-02	5.600E-02	150.1	4.93E+01	9.01E-01	8.
328	6.757	5.304E-02	3.437E-02	3.222E-02	162.3	5.06E+01	9.37E-01	17.
331	6.905	5.222E-02	3.584E-02	3.277E-02	156.6	5.07E+01	9.14E-01	5.
334	7.175	5.270E-02	2.878E-02	2.707E-02	-195.0	4.50E+01	9.41E-01	5.
337	7.242	5.218E-02	2.904E-02	2.678E-02	165.5	4.43E+01	9.22E-01	5.
340	7.451	5.318E-02	2.586E-02	2.360E-02	170.4	4.18E+01	9.13E-01	10.

Table 47 - 0 Kt Aft Cushion Pressure (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AFT CUSHION PRESSURE

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PSI)	ROOTQ0 (PSI)	AMPLITUDE (PSI)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	5.826E-02	4.630E-03	2.178E-03	160.7	1.19E+01	4.70E-01	11.
344	1.499	5.649E-02	5.078E-03	2.109E-03	142.3	1.07E+01	4.15E-01	4.
347	1.750	5.395E-02	4.911E-03	1.555E-03	154.3	9.33E+00	3.17E-01	2.
302	2.290	5.821E-02	4.803E-03	1.952E-03	163.5	5.69E+00	4.06E-01	5.
350	2.360	5.590E-02	5.100E-03	3.674E+00	79.7	1.97E+00	7.44E-01	5.
305	2.969	5.790E-02	4.874E-03	2.353E-03	137.6	6.97E+00	4.83E-01	6.
308	3.933	5.577E-02	5.674E-03	2.348E-03	156.7	5.16E+00	4.14E-01	6.
311	4.564	5.637E-02	5.421E-03	2.864E-03	151.3	5.79E+00	5.28E-01	5.
314	5.332	5.760E-02	5.238E-03	1.619E-03	131.4	3.96E+00	3.09E-01	4.
317	6.488	5.297E-02	6.235E-03	1.842E-03	154.7	3.48E+00	3.08E-01	6.
320	7.206	5.593E-02	5.226E-03	1.501E-03	142.3	2.31E+00	2.87E-01	4.
356	7.248	5.256E-02	5.648E-03	7.280E-04	119.2	1.58E+00	1.29E-01	5.
359	7.272	5.792E-02	5.093E-03	2.184E-03	145.4	3.62E+00	4.29E-01	5.
362	7.291	5.725E-02	5.551E-03	2.827E-03	-188.4	3.42E+00	5.09E-01	5.
353	7.333	5.647E-02	4.419E-03	5.769E-04	137.8	2.55E+00	1.31E-01	5.
365	7.433	5.286E-02	6.213E-03	3.482E-03	159.5	3.00E+00	5.60E-01	5.
326	8.057	5.634E-02	5.573E-03	1.134E-03	147.5	1.72E+00	2.03E-01	1.
368	8.078	5.129E-02	5.437E-03	1.384E-03	134.2	2.47E+00	2.55E-01	5.
329	8.253	5.542E-02	5.721E-03	1.396E-03	-203.6	2.67E+00	2.44E-01	3.
335	8.336	5.597E-02	4.879E-03	1.106E-03	165.9	2.64E+00	2.27E-01	4.
332	8.553	5.540E-02	5.045E-03	9.463E-04	168.4	1.68E+00	1.88E-01	2.
338	8.881	5.823E-02	5.144E-03	1.036E-03	149.0	2.63E+00	2.01E-01	1.

Table 48 - 20 Kt Aft Cushion Pressure (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AFT CUSHION PRESSURE

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PSI)	ROOTQ0 (PSI)	AMPLITUDE (PSI)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	4.640E-02	2.502E-02	2.412E-02	20.6	1.27E+02	9.64E-01	13.
301	1.506	4.324E-02	2.592E-02	2.369E-02	12.2	1.31E+02	9.14E-01	15.
342	1.530	4.482E-02	6.627E-03	4.399E-03	49.7	1.25E+02	6.64E-01	11.
348	1.757	4.815E-02	3.142E-02	2.965E-02	44.0	1.41E+02	9.44E-01	10.
351	2.243	4.539E-02	3.506E-02	3.359E-02	63.5	1.21E+02	9.58E-01	8.
303	2.273	4.245E-02	3.290E-02	3.034E-02	61.6	1.16E+02	9.22E-01	18.
306	2.938	4.610E-02	4.010E-02	3.841E-02	90.7	1.15E+02	9.58E-01	12.
309	3.790	4.391E-02	3.977E-02	3.814E-02	117.1	8.29E+01	9.59E-01	4.
312	4.360	4.704E-02	3.219E-02	3.083E-02	129.3	6.83E+01	9.57E-01	12.
315	5.073	4.452E-02	2.227E-02	2.134E-02	138.9	5.25E+01	5.27E-01	5.
318	5.790	4.497E-02	1.592E-02	1.522E-02	157.3	3.40E+01	9.56E-01	12.
354	6.233	4.637E-02	7.739E-03	5.349E-03	159.9	2.72E+01	6.91E-01	4.
366	6.260	4.010E-02	5.368E-02	4.169E-02	161.7	3.02E+01	7.77E-01	3.
360	6.290	4.718E-02	1.975E-02	1.760E-02	168.2	2.61E+01	8.91E-01	3.
357	6.361	4.726E-02	1.188E-02	1.092E-02	161.6	2.87E+01	9.19E-01	5.
363	6.372	4.040E-02	3.356E-02	2.857E-02	159.3	2.53E+01	8.51E-01	3.
321	6.397	4.565E-02	1.679E-02	1.568E-02	159.2	2.83E+01	9.34E-01	8.
327	6.789	4.445E-02	1.583E-02	1.479E-02	164.0	2.48E+01	9.34E-01	4.
370	6.899	4.477E-02	1.458E-02	1.212E-02	-191.8	2.06E+01	8.31E-01	8.
330	6.922	4.474E-02	1.575E-02	1.406E-02	167.7	2.26E+01	8.93E-01	4.
333	7.242	4.721E-02	1.318E-02	1.136E-02	168.2	1.96E+01	8.62E-01	3.
336	7.393	4.224E-02	1.177E-02	1.063E-02	165.9	1.94E+01	9.03E-01	7.
339	7.468	4.679E-02	1.160E-02	1.043E-02	-191.4	1.84E+01	8.99E-01	7.

Table 49 - 26 Kt Aft Cushion Pressure (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

AFT CUSHION PRESSURE

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (PSI)	ROOTQ0 (PSI)	AMPLITUDE (PSI)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
343	1.213	3.766E-02	3.090E-02	3.034E-02	304.0	1.48E+02	9.82E-01	2.
346	1.495	4.086E-02	3.332E-02	3.276E-02	349.8	1.67E+02	9.83E-01	9.
349	1.741	4.097E-02	3.343E-02	3.178E-02	2.1	1.50E+02	9.51E-01	8.
304	2.222	4.271E-02	4.759E-02	4.366E-02	95.4	1.60E+02	9.17E-01	16.
352	2.263	3.218E-02	4.202E-02	3.311E-02	63.2	1.21E+02	7.88E-01	26.
307	2.930	3.104E-02	4.537E-02	4.064E-02	62.0	1.24E+02	8.96E-01	10.
310	3.813	3.805E-02	6.127E-02	5.539E-02	95.4	1.19E+02	9.04E-01	10.
313	4.341	4.142E-02	5.056E-02	4.663E-02	116.7	9.87E+01	9.22E-01	12.
316	5.001	3.921E-02	3.320E-02	3.133E-02	133.2	7.35E+01	9.44E-01	10.
319	5.930	4.004E-02	2.394E-02	2.121E-02	145.5	5.01E+01	8.86E-01	7.
355	6.272	4.004E-02	1.146E-02	1.006E-02	153.9	4.19E+01	8.78E-01	3.
358	6.326	4.061E-02	1.643E-02	1.537E-02	155.6	3.91E+01	9.36E-01	9.
361	6.387	4.165E-02	3.180E-02	2.930E-02	159.4	3.95E+01	9.22E-01	5.
322	6.393	4.232E-02	2.523E-02	2.148E-02	152.8	4.08E+01	8.51E-01	9.
364	6.433	3.747E-02	5.194E-02	4.413E-02	150.6	3.88E+01	8.50E-01	8.
328	6.757	4.019E-02	2.410E-02	2.206E-02	159.0	3.47E+01	9.15E-01	17.
331	6.905	4.065E-02	2.443E-02	2.097E-02	158.2	3.25E+01	8.58E-01	5.
334	7.175	4.136E-02	1.954E-02	1.803E-02	-200.6	2.99E+01	9.23E-01	5.
337	7.242	3.810E-02	1.864E-02	1.686E-02	159.0	2.79E+01	9.05E-01	5.
340	7.451	4.149E-02	1.800E-02	1.607E-02	160.9	2.84E+01	8.93E-01	10.

Table 50 - 0 Kt Drag (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

DRAG

NOMINAL SPEED 0 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (LBS)	ROOTQ0 (LBS)	AMPLITUDE (LBS)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
300	1.491	4.294E-01	2.579E+00	1.896E+00	118.8	1.42E+00	7.35E-01	11.
344	1.499	8.865E-01	2.197E+00	2.038E+00	111.5	1.42E+00	9.28E-01	4.
347	1.750	1.831E-01	3.310E+00	2.883E+00	104.1	2.37E+00	8.71E-01	2.
302	2.290	5.192E-01	3.759E+00	2.873E+00	106.3	1.15E+00	7.64E-01	5.
350	2.360	5.803E-01	4.937E+00	3.674E+00	79.7	1.97E+00	7.44E-01	5.
305	2.969	9.776E-01	4.929E+00	2.654E-01	184.2	1.61E+00	8.07E-01	6.
308	3.933	4.126E-01	4.986E+00	4.276E+00	96.0	1.29E+00	8.58E-01	6.
311	4.564	8.316E-01	4.865E+00	3.952E+00	90.5	1.09E+00	8.12E-01	5.
314	5.332	9.732E-01	3.699E+00	3.413E+00	59.4	1.15E+00	9.23E-01	4.
317	6.488	7.715E-01	3.353E+00	3.229E+00	84.8	8.36E-01	9.63E-01	6.
320	7.206	8.893E-01	4.975E+00	4.552E+00	87.0	9.61E-01	9.15E-01	4.
356	7.248	1.876E-01	3.219E+00	3.097E+00	87.8	9.21E-01	9.62E-01	5.
359	7.272	3.799E-01	4.535E+00	3.980E+00	68.5	9.03E-01	8.78E-01	5.
362	7.291	3.698E-02	8.235E+00	6.850E+00	71.2	1.14E+00	8.32E-01	5.
353	7.333	3.604E-01	2.194E+00	1.966E+00	86.0	1.19E+00	8.96E-01	5.
365	7.433	-3.322E-01	9.128E+00	8.015E+00	66.9	9.47E-01	8.78E-01	5.
326	8.057	9.807E-01	4.774E+00	4.120E+00	82.3	8.55E-01	8.63E-01	1.
368	8.078	-4.131E-01	4.000E+00	3.363E+00	77.2	8.21E-01	8.41E-01	5.
329	8.253	7.501E-01	3.870E+00	3.503E+00	75.3	9.17E-01	9.05E-01	3.
335	8.336	7.158E-01	2.989E+00	2.687E+00	79.7	8.80E-01	8.99E-01	4.
332	8.553	1.218E+00	4.677E+00	3.714E+00	80.4	9.05E-01	7.94E-01	2.
338	8.881	7.663E-01	2.398E+00	2.256E+00	79.6	7.86E-01	9.41E-01	1.

Table 51 - 20 Kt Drag (English Units)

TWIN CUSHION SEV

REGULAR WAVE DATA

JUNE 1976

DRAW

NOMINAL SPEED 20 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (LBS)	ROOTQ0 (LBS)	AMPLITUDE (LBS)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOTQ0	NUMBER OF CYCLES
345	1.489	2.662E+01	3.955E+01	6.037E+00	284.3	4.35E+00	1.53E-01	13.
301	1.506	2.239E+01	3.482E+01	4.942E+00	249.4	3.75E+00	1.42E-01	15.
342	1.530	2.404E+01	3.836E+01	1.685E+01	188.7	6.56E+01	4.39E-01	11.
348	1.757	2.519E+01	8.307E+01	7.913E+01	276.9	5.15E+01	9.52E-01	10.
351	2.243	2.772E+01	6.181E+01	5.446E+01	56.7	2.69E+01	8.81E-01	8.
303	2.273	2.338E+01	3.684E+01	2.833E+01	56.8	1.48E+01	7.69E-01	18.
306	2.938	2.560E+01	3.021E+01	2.531E+01	76.7	1.04E+01	8.38E-01	12.
309	3.790	2.821E+01	4.544E+01	2.477E+01	101.6	7.37E+00	5.44E-01	4.
312	4.360	2.711E+01	3.329E+01	1.991E+01	99.7	6.05E+00	5.98E-01	12.
315	5.073	2.505E+01	2.894E+01	1.526E+01	111.7	5.14E+00	5.27E-01	5.
318	5.790	2.451E+01	2.748E+01	1.098E+01	131.7	3.36E+00	3.99E-01	12.
354	6.233	2.413E+01	3.371E+01	5.073E+00	145.7	3.53E+00	1.50E-01	4.
366	6.260	3.674E+01	5.041E+01	3.051E+01	129.1	3.02E+00	6.05E-01	3.
360	6.290	2.573E+01	4.471E+01	1.586E+01	143.2	3.22E+00	3.55E-01	3.
357	6.361	2.391E+01	3.426E+01	8.216E+00	140.1	2.96E+00	2.40E-01	5.
363	6.372	2.898E+01	4.347E+01	2.020E+01	122.9	2.45E+00	4.65E-01	3.
321	6.397	2.467E+01	3.166E+01	1.166E+01	137.7	2.88E+00	3.68E-01	8.
324	6.786	2.474E+01	2.682E+01	9.985E+00	137.1	2.29E+00	3.72E-01	4.
370	6.899	3.902E+01	3.753E+01	1.304E+01	153.9	3.03E+00	3.47E-01	8.
330	6.922	2.484E+01	2.906E+01	7.892E+00	140.6	1.74E+00	2.72E-01	4.
333	7.242	2.403E+01	4.099E+01	8.943E+00	143.4	2.11E+00	2.18E-01	3.
336	7.393	2.374E+01	3.435E+01	6.935E+00	143.4	1.73E+00	2.02E-01	7.
339	7.468	2.276E+01	3.804E+01	6.982E+00	151.7	1.69E+00	1.84E-01	7.

Table 52 - 26 Kt Drag (English Units)

TWIN CUSHION SEV


REGULAR WAVE DATA

JUNE 1976

DRAG

NOMINAL SPEED 26 KTS

RUN NO.	WAVE LENGTH/ CUSH LENGTH	MEAN (LBS)	ROOT00 (LBS)	AMPLITUDE (LBS)	PHASE (DEG)	TRANSFER FUNCTION	AMPLITUDE /ROOT00	NUMBER OF CYCLES
343	1.213	4.205E+01	3.135E+01	1.290E+01	210.5	8.63E+00	4.12E-01	2.
346	1.495	3.455E+01	2.263E+01	1.599E+01	229.7	1.11E+01	7.07E-01	9.
349	1.741	3.936E+01	3.294E+01	2.734E+01	249.9	1.77E+01	8.30E-01	8.
304	2.222	6.843E+00	7.417E+01	7.135E+01	339.9	3.58E+01	9.62E-01	16.
352	2.263	1.585E+01	1.340E+02	1.235E+02	358.5	6.16E+01	9.22E-01	26.
307	2.930	2.613E+01	4.430E+01	4.214E+01	63.2	1.76E+01	9.51E-01	10.
310	3.813	3.961E+01	4.960E+01	3.918E+01	87.7	1.15E+01	7.90E-01	10.
313	4.341	3.694E+01	5.005E+01	2.838E+01	102.4	8.23E+00	5.67E-01	12.
316	5.001	3.324E+01	2.434E+01	1.688E+01	107.3	5.42E+00	6.94E-01	10.
319	5.930	3.167E+01	1.872E+01	1.199E+01	117.4	3.88E+00	6.41E-01	7.
355	6.272	3.287E+01	1.400E+01	8.128E+00	126.1	4.64E+00	5.80E-01	3.
358	6.326	3.381E+01	2.008E+01	1.197E+01	122.3	4.17E+00	5.96E-01	9.
361	6.387	3.574E+01	4.217E+01	2.145E+01	129.2	3.97E+00	5.09E-01	5.
322	6.393	3.403E+01	3.496E+01	1.479E+01	124.0	3.85E+00	4.23E-01	9.
364	6.433	4.323E+01	5.814E+01	3.405E+01	123.3	4.11E+00	5.86E-01	8.
328	6.757	3.229E+01	2.629E+01	1.352E+01	125.1	2.91E+00	5.14E-01	17.
331	6.905	3.456E+01	3.480E+01	1.324E+01	120.0	2.81E+00	3.81E-01	5.
334	7.175	3.163E+01	2.402E+01	1.303E+01	127.1	2.97E+00	5.43E-01	5.
337	7.242	3.243E+01	2.377E+01	1.074E+01	128.4	2.43E+00	4.52E-01	5.
340	7.451	3.115E+01	1.974E+01	1.083E+01	130.7	2.63E+00	5.49E-01	10.



- ▼ SONIC PROBE
- PRESSURE TAPS
- ▽ IMPACT GAGES
- ACCELEROMETERS

NOTE : SEE TABLE 2 FOR TRANSDUCERS  
AND PRESSURE TAPS LOCATIONS





Figure 1 - Twin Cushion SEV Model 1 - Schematic of Transducer  
and Pressure Tap Locations

# TWIN CUSHION SEV




Figure 2 - Pitch Transfer Functions for 0, 20, 26 Knots

# TWIN CUSHION SEV




Figure 3 - Heave Transfer Functions for 0, 20, 26 Knots

# IWIN CUSHION SEV




Figure 4 - Bow Acceleration Transfer Functions for 0, 20, 26 Knots

# TWIN CUSHION SEV




Figure 5 - Relative Bow Motion Transfer Functions for 0, 20, 26 Knots

# TWIN CUSHION SEV




Figure 6 - Average Cushion Pressure Transfer Functions for 0, 20, 26 Knots

# TWIN CUSHION SEV




Figure 7 - Forward Cushion Pressure Transfer Functions for 0, 20, 26 Knots

# TWIN CUSHION SEV




Figure 8 - Aft Cushion Pressure Transfer Functions for 0, 20, 26 Knots

# TWIN CUSHION SEV




Figure 9 - Drag Transfer Function for 0, 20, 26 Knots

# TWIN CUSHION SEV




Figure 10 - Mean Drag for 0, 20, 26 Knots

# TWIN CUSHION SEV

Wave Length/Cushion Length = 7.2  
Wave Period = 3.4 sec




Figure 11 - Pitch Amplitude vs Wave Amplitude for 0, 20, 26 Knots

# TWIN CUSHION SEV

Wave Length/Cushion Length = 7.2  
Wave Period = 3.4 sec




Figure 12 - Heave Amplitude vs Wave Amplitude for 0, 20, 26 Knots

# TWIN CUSHION SEV

Wave Length/Cushion Length = 7.2

Wave Period = 3.4 sec




Figure 13 - Bow Acceleration Amplitude vs Wave Amplitude for 0, 20, 26 Knots

# TWIN CUSHION SEV

Wave Length/Cushion Length = 7.2  
Wave Period = 3.4 sec




Figure 14 - Relative Bow Motion Amplitude vs Wave Amplitude for 0, 20, 26 Knots

# TWIN CUSHION SEV

Wave Length/Cushion Length = 7.2  
Wave Period = 3.4 sec




Figure 15 - Average Cushion Pressure Amplitude vs Wave Amplitude for 0, 20, 26 Knots

# TWIN CUSHION SEV

Wave Length/Cushion Length = 7.2  
Wave Period = 3.4 sec




Figure 16 - Forward Cushion Pressure Amplitude vs Wave Amplitude for 0, 20, 26 Knots

# TWIN CUSHION SEV

Wave Length/Cushion Length = 7.2  
Wave Period = 3.4 sec




Figure 17 - Aft Cushion Pressure Amplitude vs Wave Amplitude for 0, 20, 26 Knots

# TWIN CUSHION SEV

Wave Length/Cushion Length = 7.2  
Wave Period = 3.4 sec




Figure 18 - Drag Amplitude vs Wave Amplitude for 0, 20, 26 Knots

**DTNSRDC ISSUES THREE TYPES OF REPORTS**

**(1) DTNSRDC REPORTS, A FORMAL SERIES PUBLISHING INFORMATION OF PERMANENT TECHNICAL VALUE, DESIGNATED BY A SERIAL REPORT NUMBER.**

**(2) DEPARTMENTAL REPORTS, A SEMIFORMAL SERIES, RECORDING INFORMATION OF A PRELIMINARY OR TEMPORARY NATURE, OR OF LIMITED INTEREST OR SIGNIFICANCE, CARRYING A DEPARTMENTAL ALPHANUMERIC IDENTIFICATION.**

**(3) TECHNICAL MEMORANDA, AN INFORMAL SERIES, USUALLY INTERNAL WORKING PAPERS OR DIRECT REPORTS TO SPONSORS, NUMBERED AS TM SERIES REPORTS; NOT FOR GENERAL DISTRIBUTION.**

END  
11-77